

RECORDED

MAY 1 6 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Lake

Table with columns: (County), Located In: (T20N R12W), Corner Code # (I-13). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

LIBER 003 PAGE 0374

RECORDED LAKE COUNTY, MI. SEP 12 3 11 PM '96 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Robert L. Wetherell, in a field survey on August 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked in the intersection of column L and row 12.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-13 - Section corner common to Sections 34 & 35, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
1838 - J. Hodgson, G.L.O.
Undated - George Johnson (1920's m/L)
1974 - Carl Roser, LS 12028
#1 - 20" Hemlock N36°E 31 Links
1" Iron in Road
L.C.R.C. - Liber 02, Page 222
#2 - 10" Hemlock N42°W 23 Links
#3 - 6" W Ash NW 25'
"Recovered 1-1/4" pipe & possible
(Closing corner 78 Links East)
#4 - 6" W. Ash NE 11'
G. Johnson witness"
#5 - 5" Maple N77°W 43.6'
#6 - Cedar Post due West 16-1/2'
#7 - Centerline North and South Bit. Road-East 15'
#8 - N.W. cor. Sec. 2 East 51.48'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 - Section corner common to Sections 34 & 35, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
I found a 1-1/4" pipe 15 feet West of the centerline of North and South blacktop road. Found closing corner to East at 51.65'.
Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone, #6 Found down, #7 Found in good condition, #8 Found in good condition,

ATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN Q.L.W.
DATE 8-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 - Section corner common to Sections 34 & 35, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
I placed a 3/4" x 24" rebar with Lake County Brass Cap inside of the found 1-1/4" pipe, and is accepted as a careful and faithful re-establishment of the position of the original corner.
7" W. Pine S64°E 49.10' ((60d spike in N. side)
8" Tw. Apple S33°W 38.84' (60d spike in W. side)
4" Tw. B. Oak N55°W 22.7' (60d spike in S. side)
Brass Cap Iron (Sec. cor. 2 & 3, T19N, R12W) East 51.65' #8
Centerline North and South blacktop road East 15' #7

Signed by Robert L. Wetherell
24624
Surveyor's Michigan License No.

September 5, 1996

