

MAY 1 6 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Lake

Form with columns: (County), Located In: (T20N R12W), Corner Code # (J-13). Includes sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

RECORDED LAKE COUNTY, MI. SEP 12 3 12 PM '96 REGISTER OF DEEDS

LIBERTY 003 PAGE 0375

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 6-36.

I, Robert L. Wetherell, in a field survey on August 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: J-13 - South 1/4 corner of Section 35, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

- 1839 - S. Sibley, G.L.O.
#1 - 8" B. Ash N43°W 20 Links
#2 - 10" Birch N27°E 8 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: J-13 - South 1/4 corner of Section 35, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I found metal strap iron with stones, earthenware and broken glass around it 6 feet more or less South of centerline of East and West dirt road. This position fits East 1/16 line fence running North.

I measured the following distances:

- To Southwest corner of Section 35 - 2652.02 feet
To Southeast corner of Section 35 - 2676.42 feet

I did not recover accessories No. 1 or No. 2.

NOTIFIED BY THE LAKE CO. PEER REVIEW GROUP IN ACCORDANCE WITH P.A. 345 CHAIRMAN Q. L. W. DATE 8-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 - South 1/4 corner of Section 35, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I set a 3/4" x 24" re-bar with a Lake County Brass cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 13" Cedar S44°E 32.40' (60d spike in N.E. side)
10" Cedar N48°E 54.39' (60d spike in E. side)
8" Cedar S15°W 17.77' (60d spike in E. side)
11" Cedar N65°W 88.34' (60d spike in N. side)

Signed by Robert L. Wetherell Date September 6, 1996
Surveyor's Michigan License No. 24624

