

JAN 12 1996

LIBER 003 PAGE 0331

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
LAKE COUNTY, MI.
OCT 30 2 45 PM '95
REGISTER OF DEEDS

For corners in

Lake (County)	Located In:		Corner Code #
	20N	12W	
1. Public Land Survey	T _____	R _____	K-11
	T _____	R _____	
	T _____	R _____	
	T _____	R _____	
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Wetherell, in a field survey on April 5, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11 - Section corner common to Sections 25, 26, 35 & 36, T20N, R12W - Lake Co., Mi.

1838 - S. Sibley (G.L.O.)

#1 - 22" Pine N47°W 37 Links

#2 - 20" Pine S45°E 17 Links

1911 - George Johnson, County Surveyor

Found remains of original stake

#3 - 22" Pine Stump S40°W 67 Links

#4 - 24" Pine Stump S35°E 37 Links

#5 - 37" Pine Stump N30-1/2°E 45 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 - Section corner common to Sections 25, 26, 35 & 36, T20N, R12W - Lake Co., Mi.

I found all three (3) of Surveyor Johnson's Pine Stumps (No. 3, No. 4, No. 5) and the remains of both G.L.O. stumps (No. 1 & No. 2). I set the corner using the recorded distances to all the above accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 - Section corner common to Sections 25, 26, 35 & 36, T20N, R12W - Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful perpetuation of the original corner.

6" R. Oak N18°W 49.86' (60d spike in S.W. side)


6" R. Oak N36°E 37.65' (60d spike in S.E. side)

13" Tw. W. Oak S77°E 65.89' (60d spike in N. side)

6" W. Pine S34°W 61.61' (60d spike in S.E. side)

Signed by Robert L. Wetherell Date August 29, 1995
24624

Surveyor's Michigan License No. _____



WARRANTED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 8-29-95