

MAY 18 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Lake (County), Located In: (T, R, Corner Code #), and Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

LIBER 003 PAGE 0373

RECORDED LAKE COUNTY, MI. SEP 12 3 11 PM '96 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Robert L. Wetherell, in a field survey on August 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column M and row 12.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 - 1/4 Corner common to Sections 35 & 36, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
1838 - J. Hodgson, G.L.O.
#1 - 14" Hemlock S55°E 14 Links
#2 - 10" Beech N27°W 34 Links
1995 - Robert L. Wetherell, LS 24624
L.C.R.C. - Liber 03, Page 286
Set corner in intersection of old fences North, East and West measured 2611.79' North to Sec. Cor. & 2601.82' South to Sec. Cor.
#3 - 15" Shag. Maple N4°E 33.74'
#4 - 10" Maple N32°W 26.89'
#5 - 9" Maple S2°E 16.30'
#6 - 6" Maple S72°E 6.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 - 1/4 Corner common to Sections 35 & 36, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
I found the 1/2" capped iron I had set in 1995. Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition,
This position fits well with old fence running West at South 1/16 line of Section 35.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP IN ACCORDANCE WITH P.A. 345 CHAIRMAN Q. L. W. DATE 8-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 - 1/4 Corner common to Sections 35 & 36, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
I replaced the 1/2" capped iron with a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.
15" Sag. Maple N4°E 33.74' (60d spike in E. side) #3
10" Maple N32°W 26.89' (60d spike in S. side) #4
9" Maple S2°E 16.30' (60d spike in E. side) #5
6" Maple S72°E 6.05' (60d spike in S. side) #6

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

September 5, 1996

