

**SURVEY & MONUMENTATION**

**JAN 12 1996**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**LIBER 003 PAGE 0332**

For corners in

(County)	Located In:		Corner Code #
	20N	12W	
1. Public Land Survey	T _____	R _____	L-11
	T _____	R _____	
	T _____	R _____	
	T _____	R _____	
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

**RECORDED**  
**LAKE COUNTY, MI.**  
**OCT 30 2 45 PM '95**  
*Registrar of Deeds*  
**REGISTER OF DEEDS**

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on April 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-11 - 1/4 Corner Common to Sections 25 and 36, T20N, R12W, Lake Co., Mi.

1838 - S. Sibley, G.L.O.

#1 - 16" Pine N26°E 18 Links

#2 - 8" W. Oak S58°W 11 Links

1911 - George Johnson, County Surveyor

Found remains of original stake

#3 - 24" Pine Stub N48°E 48.5 Links

#4 - 10" Yellow Pine S69°W 107 Links

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-11 - 1/4 Corner Common to Sections 25 and 36, T20N, R12W, Lake Co., Mi.


I found George Johnson's Pine Stub (scribed "B/T") No. 3 and the remains of the Red Pine (No. 4). I set the corner using the bearing and distance from Johnson's Pine Stub (#3). This position fits very well with a Pine Stump that I believe to be the original accessory No. 1. I did not recover accessory No. 2.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-11 - 1/4 Corner Common to Sections 25 and 36, T20N, R12W, Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful perpetuation of the original corner.

- 6" W. Oak N4°W 42.15' (60d spike in East side)
- 10" R. Pine S26°W 16.14' (60d spike in East side)
- 7" W. Oak S18°E 17.42' (60d spike in East side)
- 7" B. Oak S80°E 25.15" (60d spike in North side)



Signed by Robert L. Wetherell Date August 29, 1995

Surveyor's Michigan License No. 24624  
 RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
 IN ACCORDANCE WITH P.A. 345  
 CHAIRMAN R.L.W.  
 DATE 8.29.95