

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. <u>13</u> E. <u>13</u> W.	<u>K-7, L-7, M-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	, T. <u>20</u> N. <u>13</u> E. <u>13</u> W.	<u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9-7-73 19\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

<p><del>A. Description of original monument and accessories</del></p> <p><u>B. Cont. Cor. Code #15</u>  <u>Fd. "T" Ir. with Brass Tag on top.</u></p>	<p><u>C. Cont. Cor. Code #15</u>  <u>Fd. Brass "T" Ir. - Added Ced. Post w/loc. Tag.</u>  <u>2" Map. N25°W 15.77'</u>  <u>NW Cor. Conc. Blk. N50°E 88.7'</u>  <u>Cabin Fdn.</u>  <u>P. Pole w/transf. S45°E 65.70'</u>  <u>Ctr. E-W Sand Rd. Due S. 21'</u></p>
---	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p><u>K-7</u>  <u>Fd. yellow top "T" Ir. with Consumers Power Co. property tag on top &amp; 1x4" white top stk.</u></p>	<p><u>L-7</u>  <u>Fd. Geo. Brass Cor. Conc. Mon. w/brass Cap. as recorded in L. 2 - P. 15.</u></p>	<p><u>M-7</u>  <u>Fd. 1 1/2" x 18" Pipe as previously used by G. Blass.</u></p>
---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>K-7</u>  <u>Fd. C.P.C. "T" Ir. Added Ced. Guard Post w/loc. Tag.</u>  <u>13" R. Pine N42°W 48.7'</u>  <u>14" W. Oak S80°E 4.8'</u>  <u>11" B. Oak S35°W 14.3'</u></p>	<p><u>L-7</u>  <u>Blass Wit. as Rec. in L. 2 - P. 15</u>  <u>8" B. Oak S60°W 37.27</u>  <u>23" B. Oak Stp. N10°E 54.43</u>  <u>P. Pole S70°E 94.33</u>  <u>Conc. Mon. (buried) in S. edge of E-W dirt Rd.</u>  <u>DNR Set Ced Post Due N. 33' w/loc. Tag</u></p>	<p><u>M-7</u>  <u>Fd. 1 1/2" Pipe. - Added DNR. Mon. buried 7" in Sand Rd. intersection.</u>  <u>11" B. Oak N57°E 116.4'</u>  <u>7" B. Oak S55°E 113.1'</u>  <u>22" B. Oak N73°W 131.4'</u>  <u>Set Ced Post N45°E 66' w/loc. Tag</u></p>
---	--	---

SIGNED BY Carl F. Roser DATE 9-17-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

