

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LAKE

(County)	Located In:	Corner Code ##
1. Public Land Survey	T 20N R 13W	K-9
	T R	M-8
	T R	
	T R	
2. Property Controlling in Section	S 24 T R	14, 15
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, CARL T. KIISKILA, in a field survey on JUNE 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-9	M-8	14
(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)		



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9	M-8	14	15
FD 1/2" PIPE FOR THE SW COR OF S-24 AS FD & RECORDED BY C. COLE IN 1977 (LI 02, PG 304). FD REMAINS OF ALL 3 C. COLE WITS, FIT GOOD. CTR OF E-W SAND RD IS 3' NORTH. CTR OF M-37 IS 326'+/- E.	FD PIPE FOR E 1/4 S-24 AS SET BY G. BLASS IN 1966, MIDWAY & ON LINE BETW SEC CORNERS. COR FITS 1971 CERT OF SURVEY BY G. BLASS (LI 1, PG 115 & LI 107, PG 31) & 1992 CERT OF SURVEY BY R. WETHERELL (LI 03, PG 364).	ESTABLISHED THE S 1/8 COR ON EAST LINE SEC 24 PER STANDARD BLM INSTRUCTIONS. COR IS IN CTR N-S SAND ROAD.	ESTABLISHED THE SE COR OF SW 1/4 - SW 1/4 S-24 PER STANDARD BLM PROCEDURES. COR FALLS IN CTR E-W SAND TRAIL. CTR OF TRAIL S'LY IS 156'+/- WEST.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

K-9	M-8	14	15
FD 1/2" GALV PIPE.	FD 1/2" GALV PIPE IN CTR N-S SAND ROAD.	DR 5/8" X 3/4" REROD W/RLS CAP.	DR 5/8" X 3/4" REROD W/RLS CAP.
8" J PINE N30°W 31.9'	#12" B OAK N70°W 41.10'	13" OAK N50°W 39.8'	9" W OAK N25°W 28.8'
3" R PINE N25°E 41.8'	#4" B OAK N60°E 51.48'	6" J PINE S35°E 33.1'	7" J PINE N30°E 34.2'
5" J PINE S10°W 38.7'	#POWER POLE S55°E 27.05'	5" J PINE S60°W 25.8'	3" W PINE S50°E 55.1'
6" W OAK S45°W 45.3'	#12" B OAK S70°W 24.48'	SET CED POST W/LOC TAG. EAST 33'	9" W OAK S30°W 24.9'
SET CED POST W/LOC TAG. NORTH 33'	SET CED POST W/LOC TAG AT FD "T" IR W/RLS TAG. WEST 33'		SET CED POST W/LOC TAG. SOUTH 33'

##=RLS R. WETHERELL 1992 MIT.

Signed by Carl T. Kiiskila Date 5-16-97

Surveyor's Michigan License No. 33981