

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LAKE

(County)	Located In:	Corner Code #1
1. Public Land Survey	T <u>20N</u> R <u>13W</u>	<u>L-9, M-9,</u> <u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>25</u> T _____ R _____	<u>7</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on JUNE 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 L-9 M-9 M-10

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 FD CONC MON FOR S 1/4 COR S-24. FITS SURVEY DATA FROM G. BLASS SURVEYS. CTR OF E-W SAND RD IS 3' NORTH. TRAIL N-NE'LY IS 56'+/- EAST.	M-9 ACCEPTED FD PIPE FOR NE COR S-25. G. BLASS FD 1 1/2" PIPE W/BROKEN CROCKERY IN CTR DIRT ROADS N-S-E-W IN 1966.	M-10 REESTABLISHED E 1/4 COR OF S-25 MIDWAY & ON LINE BETWEEN FD SEC COR S 1/2 MILE TO N & S. CTR OF N-S SAND RD IS 3' EAST.	7 ESTABLISHED NE COR OF S 1/2 OF NE 1/4 S-25 PER STANDARD BLM PROCEDURE. COR IS IN CTR OF N-S SAND RD.
--	---	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 FD 4" DIAMETER CONC MON W/BRASS CAP. 3" J PINE N45°W 29.7' 8" B OAK N60°E 50.3' 6" B OAK S30°E 24.2' 12" J PINE S55°W 30.0 SET CED POST W/ LOC TAG. NORTH 33'	M-9 FD OLD 1 1/2" PIPE & CROCKERY IN RD INTER (N-S-E-W). #14" J PINE N72°W 88.05' 8" J PINE N20°W 73.74' #14" B OAK S25°E 75.58' NE COR 1 1/2' X 2 1/2' X 2 1/2' STEEL ELEC BOX S45°W 48.44'	M-10 DR 5/8" X 34" REROD W/RLS CAP. 16" R PINE N45°W 55.6' 14" B OAK N80°E 29.4' 6" MAPLE S40°E 46.7' 3" R PINE S50°W 53.7' SET CED POST W/ LOC TAG. WEST 33'	7 DR 5/8" X 34" REROD W/RLS CAP. 8" J PINE N75°W 31.7' 2" B CHERRY N70°E 22.1' 3" B CHERRY S75°E 17.1' 3" B CHERRY S85°W 20.7' SET CED POST W/ LOC TAG. WEST 33'
--	---	--	---

* 1966 RLS G. BLASS WIT.

Signed by Carl T. Kiiskila Date 5-16-97
 Surveyor's Michigan License No. 33981