

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAKE</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>20N</u> R <u>13W</u>	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>23</u> T _____ R _____	_____	8, 11
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on APRIL 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

8
 CERT. OF SURVEY L.3, P.117(9/17/87) C.COLE PS817615; "SURVEY MARKER SET".

11
 CERT. OF SURVEY L.3, P.117(9/17/87) C.COLE PS817615, "SURVEY MARKER SET".



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

8
 ESTABLISHED THE NW COR OF NE1/4 OF SW1/4 OF S-23 PER STANDARD BLM INSTRUCTIONS.

11
 ESTABLISHED SW COR OF NE1/4 OF SW1/4 OF S-23 PER STANDARD BLM INSTRUCTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8
 SET 5/8" x 34" REROD W/PS CAP AND BLUE CARSONITE POST W/LOCATION TAG.
 6" B.OAK (CLP 3) N15 W 8.99' (DROVE NAIL & TAG WEST SIDE).
 4" W.OAK (CLP 3) N65 E 27.09' (DROVE NAIL & TAG NW SIDE).
 9" W.OAK (CLP 4) S60 E 33.37' (DROVE NAIL & TAG NE SIDE).
 13" W.OAK S40 W 45.66' (DROVE NAIL & TAG NW SIDE).
 FD 1/2" REROD W/C.COLE PS CAP S84 21'E 10.23'.

11
 SET 5/8" x 34" REROD W/PS CAP & BLUE CARSONITE POST W/LOC. TAG.
 7" W.OAK N40 W 29.89' (DROVE NAIL & TAG NE SIDE).
 13" W.OAK N05 E 41.25' (DROVE NAIL & TAG W SIDE).
 13" B.OAK S75 E 30.17' (DROVE NAIL & TAG N SIDE).
 8" W.OAK S50 W 35.51' (DROVE NAIL & TAG NW SIDE).
 FD 1/2" REROD W/C. COLE PS CAP & TIN FN POST S79 14'E 4.77'

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 5-16-97