

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAKE</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>20N</u> R <u>13W</u>	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>23</u> T _____ R _____	<u>9, 13</u>	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on APRIL 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 9
 CERT. OF SURVEY L.02, P.07(SEPT. 9, 1976) C.COLE PS#17615, "SURVEY MARKER SET".
 13



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 9
 ESTABLISHED THE NW CORNER OF E1/2 OF SE1/4 OF S-23 PER STANDARD BLM INSTRUCTIONS (1/16 CORNER AS ESTAB. BY C.COLE IS S88 01°E, 31.88').
 13
 ESTABLISHED THE NW CORNER OF SE1/4 OF SE1/4 OF S-23 PER STANDARD BLM INSTRUCTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9
 SET 5/8"x 3/4" REROD W/PLASTIC PS CAP & SET BLUE CARSONITE POST W/LOCATION TAG.
 15° W.OAK N45 W 73.50' (DROVE NAIL & TAG SW SIDE).
 4° MAPLE N67 E 49.27' (DROVE NAIL & TAG S'LY SIDE).
 20° B.OAK S30 E 12.38' (DROVE NAIL & TAG SW SIDE).
 5° R.MAPLE(CLP 4) S55 W 19.84' (DROVE NAIL & TAG SE SIDE).
 FD 1/2" REROD W/C.COLE PS CAP & STEEL FN POST FOR GUARD S88 01°E 31.88'.

13
 SET 5/8"x 3/4" REROD W/PLASTIC PS CAP & BLUE CARSONITE POST W/LOCATION TAG.
 6° R.MAPLE N85 W 5.16' (DROVE NAIL & TAG N SIDE).
 4° R.MAPLE N20 E 12.81' (DROVE NAIL & TAG E'LY SIDE).
 5° R.MAPLE S45 E 20.30' (DROVE NAIL & TAG SW SIDE).
 6° R.MAPLE S15 W 19.94' (DROVE NAIL & TAG WEST SIDE).
 FD 1/2" REROD W/C.COLE PS CAP & TIN FN POST FOR LOT CORNER TO LOTS "H" & "F", CERT. OF SURVEY L.02, P.07 S89 16°E 15.97'.

Signed by Carl T. Kiiskila Date 5-16-97
 Surveyor's Michigan License No. 33981