

DEC 9 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in Lake	Located in:	Corner Code#	
1. Public Land Survey	T 20N	R14W	M-13
	T 20N	R 13W	A-13 ✓
	T 19N	R14W	M-1
	T 19N	R13W	A-1
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R
4. Lot No. _____	Recorded Plat _____		
5. Private Claims _____			

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0239
Dec 9 9 59 AM '99
Shirley Meyers
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on September 24, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**M-13; A-13; M-1; A-1; SEC. COR. COMMON TO TOWNSHIPS:
T20N, R14W; T20N, R13W; T19N, R14W; T19N, R13W.**

A. Description of original monument and accessories and/or subsequent restoration:

1837 - J. MULLET, G.L.O.
#1 - 12" Y. Pine N13°E 63 Links
#2 - 12" B. Oak S59°W 16 Links

1921 - G.H. Johnson, Co. Sur.
1/4" x 2" x 24" Iron
#5 - 24" B. Oak S32°W 63.5'
#6 - 10" B. Oak N24°W 21.5'

1964 - R.A. Griffin, LS 13584
L.C.R.C. - Liber 01, Page 265.
Found 1/4" x 2" x 24" iron.
Replaced with 5" Square Concrete Monument.
#7 - 7" W. Oak N70°E 90.35'
#8 - 5" W. Oak S57°E 30.50'
#9 - 4" R. Pine S89°W 39.65'
#10 - 9" W. Oak N49°W 85.40'
#11 - 5" x 7' Post - East 33'

1907 - J. Millard
"Probable remnants of stake and bearing trees, 3.17 chains South and .57 East of Temp."
#3 - 8" B. Oak S35°W 49 Links
#4 - 6" B. Oak S7°E 32-1/2 Links
S. line of Sec. 36 = 5311'
E. line of Sec. 36 = 5346'

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *R.S.W.*
DATE 10-19-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found Griffin's 5" Square Concrete Monument in the center of North and South road. I measured the East line of Section 36 = 5224'. In 1988 C. Cole, LS 17615 measured South line Sec. 36 = 4956' more or less.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found stump, #6 Gone, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition, #10, Found in good condition, #11 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the original corner.

10" W. Oak N73°E 90.33 (dock spike in N.W. side) #7
10" W. Oak S56°E 30.46' (dock spike in N.E. side) #8
8" R. Pine N89°W 36.69' (dock spike in S. side) #9
14" W. Oak N49°W 85.42' (dock spike in S.W. side) #10

Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624

