

SURVEY & REMONUMENTATION

JAN 14 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Lake

(County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 13W	D-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
LAKE COUNTY, MI.

LIBER 004 PAGE 0103
DEC 12 11 39 AM '97

Lucinda H. Dechow

REGISTER OF DEEDS.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on September 22, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 - 1/4 Corner common to Sections 8 & 17, T20N, R13W, Lake Co., Mi.

- | | |
|--------------------------------|--|
| <u>1838 - J. Brink, G.L.O.</u> | <u>1917 - George Johnson, Co. Sur.</u> |
| #1 - 10" Aspen N43°E 11 Links | Angle Iron, 20" Long |
| #2 - 10" Pine S34°E 26 Links | #3 - 6" W. Oak S58°E 110' |
| | #4 - 7" B. Oak N81°30'W 23' |

1966 - Robert Griffin, LS 13584

- L.C.R.C. - Liber 01, Page 287
 Found angle iron. Replaced with 5" Square Concrete Monument.
 #5 - 8" B. Oak North 65.10'
 #6 - 7" B. Oak N41°E 61.58'
 #7 - 8" W. Oak S12°E 29.40'
 #8 - 6" B. Oak S34°W 79.32'
 #9 - 4" x 7' Post West 33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 - 1/4 Corner common to Sections 8 & 17, T20N, R13W, Lake Co., Mi.

I found Griffins 5" Square Concrete Monument on South edge of East and West two track road.

Condition of the accessories are as follows: #1 gone, #2 Gone, #3 Gone, #4 Found Two (9" & 12") Black Oak; #5 Found dead, #6 Found in poor condition, #7 Found in good condition, #8 Found in good condition, #9 Gone.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN E.R.W.
 DATE 12-10-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 - 1/4 Corner common to Sections 8 & 17, T20N, R13W, Lake Co., Mi.

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 10" B. Oak S34°W 79.32' (dock spike in S.E. side) #8
- 10" W. Oak S6°E 29.38' (dock spike in S.W. side) #7
- 12" B. Oak N72°W 14.80' (60d spike in N. side)
- 12" B. Oak N26°W 40.45' (60d spike in S.W. side)
- 8" W. Oak N88°E 41.00' (60d spike in S. side)

igned by Robert L. Wetherell

Date 12-12-97

urveyor's Michigan License No. 24624

