

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0277

For corners in

Lake (County)	Located In:	Corner Code #	
	20N. 13W.	E-8	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

STATE OF MICHIGAN) RECORDED 14th DAY OF
 COUNTY OF LAKE) 1894 A.D. at
 O'Clock 11:30 AM.
Samuel A. DeWitt REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell in a field survey on October 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-8 - 1/4 Corner common to Sections 20 and 21, T20N, R13W, Eden Township, Lake Co., Mi.
- | | | |
|---|---|---|
| 1839 - John Brink, G.L.O.
#1 - 6" Maple N21°E 28 Links
#2 - 8" Maple S48°W 14 Links | 1983 - Robert L. Wetherell, LS 24624
Found 1/4" x 4" x 24" Flat Iron and accessories #3 and #4.
#5 - 5" R. Oak N41°E 45.77'
#6 - 10" R. Pine S33°E 65.55'
#7 - 5" W. Oak S52°W 47.09'
#8 - 5" R. Oak N76°W 39.31'
L.C.R.C. Liber 003, Page 002. | 1989 - Sammy Barnett, LS 16923
Replaced Flat Iron with
5" x 60" U.S.F.S. Concrete Mon.
#9 - 10" R. Pine S33°E 65.55' (#6)
#10 - 5" R. Oak N76°W 39.31' (#8)
#11 - 7" R. Oak N41°E 45.77' (#5)
L.C.R.C. Liber 003, Page 093. |
|---|---|---|
- 1920-1930 - George Johnson, Lake Co. Sur.
Iron For Corner
#3 - 10" B. Oak N75°E 23'
#4 - 8" W. Oak S25°E 33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 - 1/4 Corner common to Sections 20 and 21, T20N, R13W, Eden Township, Lake Co., Mi.

Found U.S.F.S. 5" x 60" Concrete Monument. Condition of the accessories is as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition, #10 Found in good condition, #11 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN *C. J. W.*
 DATE 11/5/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 - 1/4 Corner common to Sections 20 and 21, T20N, R13W, Eden Township, Lake Co., Mi.

I accepted the U.S.F.S. 5" x 60" Concrete Monument as a substantial monument for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

7" R. Oak N41°E 45.57' (Dock Spike in N.W. side of tree) (#5 & #11)
 7" R. Oak N71°W 39.25' (Dock Spike in S. side of tree) (#8 & #10)
 11" R. Pine S33°E 65.10' (Dock Spike in E. side of tree) (#6 & #9)
 16" R. Oak S9°E 34.71' (60d spike in E. side of tree)
 14" B. Oak N73°E 22.72' (60d spike in S. side of tree) (#3)

Signed by *Robert L. Wetherell* Date 11/9/94
 Surveyor's Michigan License No. 24624

