

REGISTERED CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In:

Corner Code #

	T 20N R 13W	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
19	S 23 T _____ R _____	9, 13
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Recorded Plat _____

_____, in a field survey on APRIL 29, 1997 do hereby state that under Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in accordance with the rules and rules therefore as required in the current manual of survey instructions of the Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or a decree of a Court of Law established in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Surveying Act or by a Decree of a Court of Law; established, re-established, monumented, and recorded below:

corners, all in the same town and range, may be recorded

monument and accessories and/or subsequent restoration:

P.07(SEPT. 9, 1976) C.COLE PS#17615,

13

evidence found and/or method applied in restoring or reestablishing corner:

13

RECORDED CORNER OF E1/2 OF SE1/4 OF S-23 PER STANDARD BLM INSTRUCTIONS. ESTABLISHED THE NW CORNER OF SE1/4 OF SE1/4 OF S-23 PER STANDARD BLM INSTRUCTIONS.

monument and accessories established to perpetuate locating the position of the corner:

13

PLASTIC PS CAP & SET BLUE CARSONITE POST	SET 5/8" x 3/4" REROD W/PLASTIC PS CAP & BLUE CARSONITE POST W/LOCATION TAG.
50' (DROVE NAIL & TAG SW SIDE).	6" R.MAPLE N85 W 5.16' (DROVE NAIL & TAG N SIDE).
27' (DROVE NAIL & TAG S'LY SIDE).	4" R.MAPLE N20 E 12.81' (DROVE NAIL & TAG E'LY SIDE).
38' (DROVE NAIL & TAG SW SIDE).	5" R.MAPLE S45 E 20.30' (DROVE NAIL & TAG SW SIDE).
19.84' (DROVE NAIL & TAG SE SIDE).	6" R.MAPLE S15 W 19.94' (DROVE NAIL & TAG WEST SIDE).
PLASTIC PS CAP & STEEL FN POST	FD 1/2" REROD W/C.COLE PS CAP & TIN FN POST FOR LOT CORNER TO
1.88'.	LOTS "H" & "F", CERT. OF SURVEY L.02, P.07 S89 16'E 15.97'.

T. Kiiskila

Date 5-16-97

33981

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

