

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 20 N. R. 14 W.	G-7; H-7
2. PROPERTY CONTROLLING IN SECTION _____	15 T. 20 N. R. 14 W.	11; 12
3. MISCELLANEOUS PROPERTY IN SECTION _____	15 T. 20 N. R. 14 W. Code's 11 & 15; N00°05'W, 800.0' from 15	*(between Cor.
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Feb. 25, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Feb. 25, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration:  
C. (continued)

12	*
Fd. P.A.S. Mon. (4"X4" Conc. Mon.w/Brass Cap) & old ced.post	Fd. P.A.S. Mon. (4"X4" Conc. Mon. w/Brass Cap) & old ced.post
12" W. Oak S25°W 14.3	10" W. Oak N40°E 3.3
16" B. Oak N25°E 22.0	8" R. Oak S70°E 4.4

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-7 Fd. Shadko P.A.S. monument buried in N-S B.Top road.
- H-7 Fd. U.S.F.S. Monument.
- 11 Fd. Shadko Public Fishing Site Monument (1941) for the Ctr. of SW 1/4.
- 12 Fd. Shadko Public Fishing Site Monument (1941).
- \* Fd. Shadko Public Fishing Site Monument (1941) for the NE Cor. of the S. 800.0' of SW 1/4-SW 1/4 Sec. 15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7	H-7	11
Fd. Shadko P.A.S. Mon. & raised with 1"X7" pipe	Fd. 4"X4" Conc. Mon.w/Brass Cap & added Ced. Post	Fd. P.A.S. Mon. (4"X4" Conc. Mon. w/Brass Cap) & old Ced.post
26" B.Oak N55°W 70.85	13" W. Oak N68°W 50.92	9" W. Oak N75°W 27.3
12" B.Oak S59°W 72.50	18" W. Oak N18°W 22.09	Twin Oak S65°E 16.8
P.Pole N42°E 51.20	P.Pole N75°E 90.50	
Ctr. N-S Bit. rd. Due E 3'+		
Fd. 4"X4" U.S.F.S. Post S50°W 47'		


SIGNED BY Carl F. Roser DATE 4-19-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)  
ELK TOWNSHIP  
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_