

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                       | LOCATED IN--:     | CORNER CODE NUMBER                 |
|---|-------------------|------------------------------------|
| 1. PUBLIC LAND SURVEY_____              | T. 20 N. R. 14 W. | G-6                                |
| 2. PROPERTY CONTROLLING IN SECTION 15   | T. 20 N. R. 14 W. | 10; 15                             |
| 3. MISCELLANEOUS PROPERTY IN SECTION 15 | T. 20 N. R. 14 W. | * 799.9'N of G-7 & 1874.8's of G-6 |
| 4. LOT NO. _____, RECORDED PLAT _____   |                   |                                    |
| 5. PRIVATE CLAIMS _____                 |                   |                                    |

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 27, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on June 27, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
C. (continued)

\*

|   |          |       |
|---|----------|-------|
| Fd. P.A.S. Mon. & raised w/1" X11" pipe |          |       |
| 5" W. Pine                              | N40°E    | 53.38 |
| 9" W. Oak                               | S55°E    | 61.19 |
| Fd. P.A.S. Mon & Ced. post              |          |       |
|   | N89°41'E | 33.05 |
| ⊕ N-S bit. rd.                          | Due W    | 1.8'  |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-6 Fd. "T" Ir. buried in N-S B.Top rd. Fits 1/8 Cor. & Sec. Cor. to So. & previous Survey's by Blass and by Shadko.

10 Recovered 3/4" Pipe buried in N-S B.Top Rd. for S 1/8 Cor. on W. Line Sec. 15.

15 Fd. Shadko Conc. fishing site monument with bronze cap stamped 43-5, 1941.

\* Recovered Shadko P.A.S. buried in N-S B. Top Rd.; for NW Cor. of S 800' of SW 1/4-SW 1/4 of Sec. 15. *Mon.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| G-6                                      | 10  | 15  |
|--|---|---|
| Fd. 3/4" "T" iron & raised w/1"X7" pipe. | Fd. remains of 3/4" pipe & raised w/ 1/2"X18" pipe, | Fd. 4"X4" Conc.Mon w/brass cap & old ced. post. |
| 14" R.Pine N55°E 69.77                   | 6" R.Pine N50°W 49.85                               | 8" Cedar in clump of 4 S30°W 22.74              |
| 8" W.Oak Due E 54.24                     | 6" W. Oak S73°W 37.06                               | 11" Cedar S80°W 36.10                           |
| 13" W.Pine Due W 71.24                   | Set Ced.post w/loc.tag beside old cor. post         | SW'ly River Bank                                |
| Ctr.N-S rd. Due W 1.5'                   | Due W 33  | Due W 4'  |
| Set Ced.Post W/loc.tag behind Fd."T"iron | Ctr. N-S bit. rd.                                   |   |
| Due E 33                                 | Due W 1/2'  |   |

SIGNED BY Carl F. Roser 4-19-78 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)  
ELK TOWNSHIP  
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_