

MAY 18 1998

LIBER004 PAGE 0122

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Lake

Table with columns: Located In: (County), Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REGISTERED LAKE COUNTY, MI. APR 14 3 04 PM '98 REGISTER OF DEEDS Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Robert L. Wetherell, in a field survey on Jan. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13 - Section corner common to Sections 31 & 32, T20N, R14W, Elk Twp., Lake Co., Mi.

1837 - Mullett, G.L.O.

- #1 - 10" Sugar N56°E 56 Links
#2 - 18" Hemlock N42°W 47 Links

1908 - J.W. Nicholson, Co. Sur.

- "Found Old Stakes"
#3 - 7" Hemlock N6°W 47-1/2 Links
#4 - 6" Beech N38°E 63-1/2 Links

1965 - Robert Griffin, LS 13584

Found a badly rotted square stake 23.76' West of corner common to Sec. 5 & 6 of T19N, R14W. No accessories for this corner given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 - Section corner common to Sections 31 & 32, T20N, R14W, Elk Twp., Lake Co., Mi.

I found a 1" pipe which Robert Griffin calls for as an accessory to the corner common to Sections 5 & 6 of T19N, R14W, (L.C.R.C. - Liber 01, Pg. 173). I presume Griffin replaced the rotted wood stake he found with this pipe. Griffin's monument for the corner of Sections 5 & 6 of T19N, R14W is 23.76 feet East.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found Stump, #4 Found Stub (10" diameter).

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP IN ACCORDANCE WITH P.A. 345 CHAIRMAN R.L.W. DATE 4-9-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 - Section corner common to Sections 31 & 32, T20N, R14W, Elk Twp., Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap inside of the 1" pipe, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 10" Cedar N17°E 18.03' (60d spike in W. side)
11" Cedar N75°W 30.04' (60d spike in N.E. side)
7" Maple (in clump) S21°E 12.15' (60d spike in W. side)
10" Beech N70°E 76.96' (dock spike in N. side)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 4-14-98

