

REG 28 1000

SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0177

For corners in  
Lake \_\_\_\_\_

Located In:	Corner Code #
T <sup>20N</sup> R <sup>14W</sup>	E-4
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

RECORDED  
LAKE COUNTY, MI.  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

Oct 29 4 40 PM '98  
*Frederick H. Robinson*

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Wetherell, in a field survey on March 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- E-4 - 1/4 Corner common to sections 8 & 9, T20N, R14W, Elk Twp., Lake Co., Mi.
    - 1839 - J. Brink, G.L.O.      Undated - G. Johnson, Co. Sur.
    - #1 - 10" W. Pine S40°W 12 Links      3/4" Iron Rod
    - #2 - 10" W. Oak N51°E 16 Links      #4 - 8" W. Oak N68°E 147 Links
    - 1907 - Millard, Co. Sur.      1970 m/L - Gerald Gray, LS 17741
    - Found stake and pine stump with scar and remnants of oak.      Set Concrete Monument in fence intersection.
    - #3 - 20" W. Pine N47°W 65 Links      No accessories given.

1971 - G. Blass, LS 5489  
L.C.R.C. - Liber 02, Pg. 2.  
Found concrete Monument in fence corner.  
#5 - 15" Maple S74°W 53.12'  
#6 - 18" Maple S20°W 67.94'  
#7 - 5" Maple S77°E 33.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

E-4 - 1/4 Corner common to sections 8 & 9, T20N, R14W, Elk Twp., Lake Co., Mi.

I found a 4" x 36" Concrete Monument in fence corner (North and East)

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition, #6 Found 24" R. Oak with nail and cap, #7 Found in good condition.

VALIDATED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN *R.S.W.*  
DATE 10-27-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 - 1/4 Corner common to sections 8 & 9, T20N, R14W, Elk Twp., Lake Co., Mi.

I accepted the 4" Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 18" Tw. Maple S82°W 53.07' (60d spike in N. side) #5
- 13" W. Oak N62°W 62.89' (60d spike in N. side)
- 13" Maple S65°E 33.89' (60d spike in S. side) #7
- 12" Tw. W. Oak S13°E 40.10' (60d spike in W. side)
- 24" R. Oak S28°W 67.75' (Nail and Cap in E. side) #6

Signed by Robert L. Wetherell  
Surveyor's Michigan License No. 24624

Date 10-29-98

