

SURVEY & REMONUMENTATION

MAY 29 1998

LIBER 004 PAGE 0139

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>14W</u>	G-3
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

STATE OF MICHIGAN) RECORDED 14 DAY OF
COUNTY OF LAKE) April 19 98 A.D. at
O'clock 3:05 P.M.
James H. Nelson REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on March 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-3 - Section corner common to Sections 3, 4, 9 & 10, T20N, R14W, Elk Twp., Lake Co., Mi.
 1839 - J. Brink, G.L.O. 1907 - Millard, Co. Sur.
 #1- 14" W. Pine N25-1/2°E 15 Links "Stake and down bearing tree with scar. Road runs North, South and partly opened to East".
 #2 - 14" W. Pine S56°W 22 Links #3 - 33" W. Pine S33°W 79 Links
 1908 - J.W. Nicholson, Co. Sur.
 "This corner is corrected to be right one of original witness trees with marks lying nearby. Stake at intersection of highways.

(SEE OVER FOR CONTINUATION OF "A")
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3 - Section corner common to Sections 3, 4, 9 & 10, T20N, R14W, Elk Twp., Lake Co., Mi.

I found Griffin's 5" Concrete Monument at the intersection of roads East, West, North and South. Position fits well with accessories found.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone, #6 Found in good condition, #7 Gone, #8 Found in good condition, #9 Found bent, #10 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 - Section corner common to Sections 3, 4, 9 & 10, T20N, R14W, Elk Twp., Lake Co., Mi.

I accepted the 5" Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

20" R. Oak S41°W 85.55' (dock spike S.E. side) #8

P. Pole S46°E 47.50' (nail & washer) #7

S.W. cor. Concrete Slab S34°E 59.90'

U.S.G.S. Concrete Monument N20°E 128.55' - #6

Signed by 4" x 4" Treated Post N53°E 46.60' #10

Surveyor's Michigan License No. 24624

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 285
CHAIRMAN R.L.W.
DATE 4/9/98

Date 4-14-98

