

SURVEY & REMONUMENTATION

DEC 9 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0238

DEC 9 9 59 AM '99

Alfred J. Myers
REGISTER OF DEEDS

For corners in <u>Lake</u>	Located in:	Corner Code#	
1. Public Land Survey	<u>T20N</u>	<u>R 14W</u>	<u>L-13</u>
	<u>T</u>	<u>R</u>	
	<u>T</u>	<u>R</u>	
	<u>T</u>	<u>R</u>	
2. Property Controlling in Section	<u>T</u>	<u>R</u>	
	<u>S</u>	<u>T</u>	<u>R</u>
3. Miscellaneous Property in Sec.	<u>S</u>	<u>T</u>	<u>R</u>
	<u>S</u>	<u>T</u>	<u>R</u>
4. Lot No. _____ Recorded Plat			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on September 21, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

L-13 - S. 1/4 Corner Section 36, T20N, R14W, Elk Twp., Lake Co., Mi.

A. Description of original monument and accessories and/or subsequent restoration:

1837 - J. Mullett, G.L.O.
#1 - 7" W. Pine N48°E 50 Links
#2 - 7" W. Pine N11°W 20 Links

1907 - J. Millard, Deputy Co. Sur.
"Probable bearing tree and blazes"
1908 - J.W. Nicholson
#3 - 8" B. Oak S36°W 94 Links

1965 - R.A. Griffin, 13584
"Found old cedar stake" and stump of accessory No. 2. Also identified accessory No. 3.
Set Concrete Monument.
#4 - 4" R. Pine S74°E 34.96'
#5 - 7" R. Oak S35°W 63.42'
#6 - 5" Maple N22°W 75.43'
#7 - Face of Pine Stump S34°E 5.27'
(Scribed "1/4S. BT 5FT")

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 10-19-99

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found Griffin's Concrete Monument. I measured 2313.50 feet East to the Township Corner - 1998 Measurement
I measured 5067.26 feet North to North 1/4 Corner Sec. 36 - 1998 Measurement

Condition of the accessories are as follows: #1 Gone, #2 Found depression in ground, #3 Gone, #4 Found in good condition #5 Found in good condition, #6 Found in good condition. #7 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted Griffin's Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 6" R. Pine S72°E 34.96' (Dock spike in S. side) #4
- 12" R. Oak S40°W 63.42' (Dock spike in N.W. side) #5 - Griffin identified as a sprout from accessory #3
- 9" Maple N19°W 75.43' (Dock spike in N.E. side) #6
- 15" B. Oak N37°E 38.83' (60d spike in N.W. side)

Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624

