

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	20 T. 6 N. 9 E. S. 1, R. 1 W.	E-9, D-9
2. PROPERTY CONTROLLING IN SECTION	20 T. 6 N. 9 E. S. 1, R. 1 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>E-9 Found 1/2" rod Witnesses from Bernard Griggs Jr. S 75°E - 24.3' - Sign post S 25°E - 75.3' - 36" Oak S 85°W - 25.88' - 30" Oak Set 4" x 36" Conc. monument w/alum. cap</p>	<p>D-9 Found nothing Set 4" x 36" conc. monument w/alum. cap by projection from N 1/4 corner through existing center section at intersection with South section line.</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>E-9 SE Cor. 4" x 36" Conc. monument S75°E - 25.64 - 6" B. Cherry S37°E - 25.41' - 5" Twin Hickory S45°W - 11.04' - 5" Twin Basswood N84°W - 33.09' - 5" W. Oak</p>	<p>D-9 S 1/4 corner 4" x 36" conc. monument w/alum. cap S70°W - 25.21' - 18" W. Oak N1°E - 14.21' - 12" Sassafrass N83°E - 35.95' - 20" B. Oak S60°E - 17.30' - 10" Hickory N83°30"E - 148.44 - Fence corner Fence going N, S, & E.</p>
---	--

16. S 1/8 cor. of SE 1/4 4" x 36" conc. mon.
 N80°E - 75.38' - 16" Hickory
 S23°W - 41.28' - 6" Poplar
 N34°E - 51.68' - 5" Poplar
 S23°W - 34.00' - 9' Creek

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

