

MAR 23 2000

SECTION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
99 DEC 23 AM 9: 11

For corners in

<u>Lapeer</u> (County)	Located In: Hadley Township	Corner Code #
1. Public Land Survey	T6N R9E E-1	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

501

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on August 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 9" Sugar N35°E 12 Links; 11" Ironwood S34°E 22 Links
- 1.) 1988-Kennedy, PS #17623; LCRC L.004, Pg.147 - Set a 1/2" Iron
- 2.) 1998-Kennedy, PS #17623; LCRC for (E-13 Elba Twp.) L.0006, Pg.0071 - Fnd a 1/2" Iron Rod
- 3.) 1997-Elrich, PS #18986; Survey L.0012, Pg.0177 - Fnd a 1/2" Iron Rod
- 4.) 1998-Hay, PS #41101; Survey L.0012, PG.0685 - Fnd a 1/2" Iron rod, used same wit as 1997 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod in the existing centerline of Stewart Road extending to the East & West, which has a gravel surface, also found second 1/2" Iron Rod 3.620 feet to the East. Corner common to Sections 32 & 33, T7N, R9E, Elba Township (E-13) is located 364.40 feet to the East. E-1 as found is 0.67 feet South of the town line.

Witnesses from LCRC #1, Survey #3 & 4 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

E-1 to D-1

No GLO  
No recorded distances  
2634.90 Ft. (MEA 1998)

E-1 to F-1

No GLO  
No recorded distances  
2653.27 Ft. (MEA 1998)

E-1 to E-13

GLO = 104 Links or 68.64 Ft.  
Recorded Surveys by Harold N. Elrich, PS #18986 dated 8/25/97 & Michael G. Hay, PS #41101 dated 8/22/98  
364.40 Ft. (MEA 1998)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation, #17623

N08°W 32.70' Set Mag Nail & Remon Washer NE face 10" Ash  
N61°W 69.10' Set Mag Nail & Remon Washer SW face 12" Ash  
S22°E 29.65' Set Mag Nail & Remon Washer SW face 9" Elm  
S30°W 54.70' Set Mag Nail & Remon Washer NW face 42" Oak  
East 364.40 feet corner common to Sections 32 & 33, T7N, R9E, Elba Twp. (E-13)

East 3.62 feet fnd 1/2" Iron Rod  
South 33.00 feet fnd 1/2" Iron Rod

RAY DAVIS P.S. CO. SURVEYOR  
DATE 10-21-99

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: Huston K. Kennedy Date 11-19-99  
Surveyor's Michigan License No. 17623