

MAR 23 2000

SECTION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lapeer Located In: Hadley Township Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T <u>6N</u>	R <u>9E</u>	H- <u>1</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

RECEIVED FOR RECORD  
00 JAN 17 AM 9:05

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

*H-1*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on August 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; No post was set, no witnesses  
1.) 1978-Henderson, PS #16043; LCRC L. 003, Pgs.472 & 473 - Fnd a 1/2" Iron Rod  
2.) 1976-Elrich, PS #18986; Survey L.003, Pg.605 - Fnd a 1/2" Iron Rod, no witnesses  
3.) 1978-Henderson, PS #16043; Survey L.004, Pg.954 - Fnd a 1/2" Iron Rod, used same wit as 1978 LCRC  
4.) 1980-Pangus, PS #21578; Survey L.005, Pg.922 - Fnd a 1/2" Iron Rod, used same wit as 1978 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (Con't on back side)  
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod in the existing centerline of Stewart Road extending to the East & West, which has a gravel surface, also a old tree-fence row extending to the South. The South 1/4 corner of Section 34, T7N, R9E, Elba Township (H-13) is located 298.87 feet to the East. H-1 as found is 0.96 feet to the South on the town line.

Witnesses from Survey #6 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

H-1 to G-1  
No GLO  
No recorded distances  
2624.45 Ft. (MEA 1998)

H-1 to H-13  
No GLO  
No recorded distances  
298.87 Ft. (MEA 1998)

H-1 to I-1  
No GLO  
No recorded distances  
2662.77 Ft. (MEA 1998)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
H-1 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County  
Remonumentation, #17623  
N10°W 106.26' Set Mag Nail & Remon Washer West face Power Pole  
N48°E 85.18' SE corner of house #4244  
N73°E 179.18' Set Mag Nail & Remon Washer South face 19" Oak  
S65°E 71.76' Set Mag Nail & Remon Washer North face 19" Cherry  
East 298.87' South 1/4 corner of Section 34, T7N, R9E, Elba Twp. (H-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature] Date 10-22-99  
Surveyor's Michigan License No. 17623

SURVEY &  
REMONUMENTATION

MAR 23 2000

SECTION

Town 6 North, Range 9 East, Hadley Township H-1

- 5.) 1980-Pangus, PS #21578; Survey L.005, Pg.924 – Fnd a ½" Iron Rod, used same wit as 1978 LCRC
- 6.) 1987-Elrich, PS #18986; Survey L.007, Pg. 714 – Fnd a ½" Iron
- 7.) 1991-Carlson, PS #9189; Survey L.009, Pg.516 – Fnd a ½" Iron Rod, used same wit as 1978 LCRC
- 8.) 1996-Elrich, PS #18986; Survey L.0011, Pg.0730 – Fnd a ½" Iron Rod, used same wit as 1978 LCRC
- 9.) 1998-Hay, PS #41101; Survey L.0012, Pg.0575 – Fnd a ½" Iron Rod, used same wit as 1978 LCRC
- 10.) 1999-Powell, PS #44298; Survey L.0013, Pg.0130 – Fnd a ½" Iron Rod, used same wit as 1978 Survey
- 11.) 1995-Gravlin, PS #23510; Unrecorded Survey – Fnd a ½" Iron Rod, used same wit as 1978 LCRC
- 12.) 1996-Kennedy, PS #17623; Unrecorded LCRC for (H-13 Elba Twp.) – Fnd a ½" Iron

RECORDED  
APPROVED FOR FILING  
COUNTY CLERK  
\_\_\_\_\_  
RAY DAVIS, S.P.S. CO. SURVEYOR  
DATE 10-21-99

1999-10-21  
10:11 AM  
10:11 AM