

MAR 23 2000

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lapeer</u> (County)	Located In: Hadley Township	Corner Code # L-1
1. Public Land Survey	T6N R9E	L-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

00 JAN 17 AM 9:06

Melissa DeVaugh

REG. DEEDS
LAPEER COUNTY, MICHIGAN

461

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on August 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1817-GLO Wampler, D.S.; No post was set, no witnesses
 - 1.) 1995-Kennedy, PS #17623; LCRC for (L-13 Elba Twp.) L.0005, Pg.0234 - Fnd a 1/2" Iron Rod
 - 2.) 1993-Flint Surveying; Unrecorded Survey - Object found not stated, no witnesses
 - 3.) 1993-Unrecorded witnesses - Set a 1/2" Re-bar w/CHC
 - 4.) 1995-Flint Surveying; Unrecorded Survey - Fnd a 1/2" Re-bar, used same wit as 1993 unrecorded witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod w/cap #9189 in the existing centerline of Sutton Road extending to the East & West, which has a gravel surface, also a fence-tree row extending to the South. South 1/4 corner of Section 36, T7N, R9E, Elba Township (L-13) is located 211.76 feet to the East. L-1 as found is 0.59 feet South of the town line.

Witnesses from 3 & 4 were used to recover and verify the location of the found 1/2" Iron Rod w/cap #9189.

I accepted the found 1/2" Iron Rod w/cap #9189 as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

L-1 to K-13
No GLO
No recorded distances
2639.49 Ft. (MEA 1995)

L-1 to M-1
No GLO
Unrecorded Survey by Flint Engineering dated 7/26/93 = 2638.65 Ft.
2638.66 Ft. (MEA 1995)

L-1 to L-13
No GLO
211.76 Ft. (MEA 1995)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- L-1 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation, #17623
- N55°E 49.05' Set Mag Nail & Remon Washer SE face 10" Walnut
 - S50°E 54.72' Set Mag Nail & Remon Washer NE face 12" Hickory
 - S05°E 47.72' Set Mag Nail & Remon Washer West face 13" Ash
 - S48°W 62.20' Set Mag Nail & Remon Washer NW face 10" Walnut
- East 211.76 feet South 1/4 corner of Section 36, T7N, R9E, Elba Twp. (L-13)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 11-22-99