

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 30 AM 8:26

LIBER NO. 05 PAGE NO. 129
Hester DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

Lapeer
(County)

Located in Hadley
Twp.

Corner Code #

- | | | | |
|---------------------------------------|-----|------|-----|
| 1. Public Land Survey | T6N | R 9E | M-6 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Sec | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	16		17		18		19		20			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

I, Huston K. Kennedy, in a field survey on June 15 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law, established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 16" Black Oak North 14 Links; 18" Black Oak S87°E 48 Links
1.) 1973-Henderson, P.S. #16043; LCRC L.002, Pg.195 - Set 1/2" Iron
2.) 1973-Henderson, P.S. #16043; Survey L.2, Pg.142 - Same wit as 1973 LCRC

PEER GROUP
APPROVED LAND CORNER
PA 245 OF 1990
LAPEER COUNTY

H.K. Kennedy
RAY DAVIS P.S. CO. SURVEYOR
DATE 11-29-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994-Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 3" deep in the centerline of Baldwin Road extending North
South. Found second Iron Rod 78.18' South in the intersection of the centerline of Baldwin & Kile Roads to the East, which are
both gravel roads. The found second Iron Rod is being used as the West 1/4 corner of Section 18, T6N, R10E.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6
I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623
M-6
S40°E 60.11' Set PK & Remon. Washer NE face Guide Pole
S80°E 29.24' Set PK & Remon. Washer SW face 38" Oak
N86°E 26.89' Set PK & Remon. Washer NW face 41" Oak
N43°W 47.95' Top of Michigan Bell Riser

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the
position of the original corner.



Signed by *H.K. Kennedy* Date October 3, 1994
Surveyor's Michigan License No. 17623

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 19
REVISED MAY 14, 19
REVISED JAN. 19

LIBER 0005 PAGE 0129