

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

94 NOV 30 AM 8: 27

LIBER NO. 05 PAGE NO. 130  
*Malissa De Vough*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in

<u>Lapeer</u> <small>(County)</small>	Located In: <u>Hadley</u> Twp.	Corner Code # <u>M-7</u>
1. Public Land Survey	T <u>6N</u> R <u>9E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	6	5	4	3	2					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on June 15, 19 94  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law, established, re-established, monumented, re-monumented, recovered, found as  
expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessions and/or subsequent restoration:

- 1817-GLO Hampler, D.S.; Set Post; 12" White Oak N30\*W 3.82 Chains; 38" White Oak N43\*W 0.72 Chains  
1.) 1973-Henderson, P.S. #16043; LCRC L. 002, Pg.195 - Fnd an Iron  
2.) 1974-Kennedy, P.S. #17623; LCRC L.002, Pg.647 - Fnd 1/2" Iron Pin  
3.) 1974-Kennedy, P.S. #17623; Survey L.002, Pg.824 - Same wit as 1974 LCRC  
4.) 1973-Henderson, P.S. #16043; Survey L.002, Pg.142 - Same wit as 1973 LCRC  
5.) 1986-Gravlin, P.S. #23510; Survey L.007, Pg.274 - Fnd an Iron  
6.) 1986-Elrich, P.S. #18986; Survey L.007, Pg.244 - Same wit as 1973 LCRC  
7.) 1986-Elrich, P.S. #18986; Survey L.007, Pg.245 - Same wit as 1973 LCRC  
8.) Lapeer County Road Commission Unrecorded Notes - Fnd 1/2" Iron

**PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY**  
*[Signature]*  
**RAY DAVIS P.S. CO. SURVEYOR**  
DATE 11-29-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 4" deep in the centerline of Baldwin Road extending to the  
North & South, which is a gravel surface, and 49' South of driveway for house #4491. Also found second 1/2" Iron Rod 64.90'  
the South, which can be accepted as the Northwest corner of Section 19 & Southwest corner of Section 18, T6N, R10E.


Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessions established to perpetuate locating the position of the corner:

- M-7  
I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County, Michigan #1762  
M-7  
S57°E 25.83' Set PK & Remon. Washer NE face Clump 15" Cherries  
S82°W 44.63' Set PK & Remon. Washer North face 11" Cherry  
N42°W 51.56' Set PK & Remon. Washer SW face 46" Oak  
N22°W 89.93' Set PK & Remon. Washer NE face 29" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best evidence of the  
position of the original corner.



Signed by *[Signature]* Date October 3, 1994  
Surveyor's Michigan License No. 17623