

SURVEY &
REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 30 AM 8:29

LIBER NO. 05 A SE NO. 122
Holton & Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

Lapeer
(County)

Located In: Hadley
Twp.

Corner Code ##

- | | | | |
|------------------------------------|------|------|-----|
| 1. Public Land Survey | T 6N | R 9E | M-9 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on June 15, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 26" White Oak S35*W 34 Links; 20" Black Oak N06*W 18 Links
1.) 1974-Kennedy, P.S. #17623; LCRC L.002, Pg.489 - Fnd 1/2" Iron
2.) 1987-Kennedy, P.S. #17623; LCRC L.004, Pg.125 - Fnd 1/2" Iron
3.) 1986-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

PEER GROUP
APPROVED LAND CORNER
PK 345 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR

DATE 11-29-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 1' deep in the centerline of Brocker Road extending to the East & West, which is a gravel surface, and 1.10' West of the centerline of Baldwin Road extending to the North & South, which has a gravel surface. Also found second 1/2" Iron Rod 4.46' to the South, which is the Northwest corner of Section 30 & the Southwest corner of Section 19, T6N, R10E.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- M-9 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623.
M-9
S44°E 59.20' Set PK & Remon. Washer NE face 26" Oak
S46°W 40.53' NW Corner Concrete Fence Post
N52°E 45.00' Set PK & Remon. Washer NW face 39" Oak
N41°E 76.68' Set PK & Remon. Washer NW face 9" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date October 14, 1994

Surveyor's Michigan License No. 17623



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983

LIBER 0005 PAGE 0132