

SURVEY & REMONUMENTATION

1993

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

COMMISSION
For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6</u> N R <u>9</u> E	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

93 DEC 30 AM 10:22
LIBER NO. 5 PAGE NO. 54
Melissa Miles
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 GLO - Wampler, D.S.; Set 1/2 mile post; 12" Aspen S09°W 48 lks., 12" Black Oak East 68 lks.
1986 Kennedy, P.S. #17623; LCRC L.4, Pg.125 - Set 1/2" iron rod from previous survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" iron rod in centerline of Baldwin Road, which is gravel, with a fence line extending to the West.
Found 2 previous wits which verify that the rod is in the same position as the 1986 LCRC.

I accepted the fnd 1/2" iron rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 - 1/2" x24" iron rod with 3" diameter brass cap
N29°E - 51.60' Set nail w/remon tag above existing witness in SE face 24" Maple
S66°E - 31.47' Set nail w/remon tag in N. face 11" Cedar
S18°E - 77.88' Set nail w/remon tag above existing witness in SW face 27" Maple
S19°W - 81.27' Set nail w/remon tag in E. face 28" Maple
N21°W - 153.23' Set nail w/remon tag above existing witness in E. face Power Pole



Signed by *Huston K. Kennedy* Date 11/24/93

Surveyor's Michigan License No. 17623

LIBER **005** PAGE **54**