

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE RECEIVED FROM RECORD
Filing Requirement of Act 74, Mich. P.A. 1970

98 NOV 25 AM 9:20

SECTION

For corners in

<u>Lapeer</u> (County)	Located In: Metamora Township	Corner Code #	
1. Public Land Survey	T6N	R10E	A-10
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

405

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; No post was set
1.) 1976-Kennedy, PS #17623; LCRC L.003, pg 266 - Fnd 1/2" Iron Rod
2.) 1979-Buckerfield, PS #10868; LCRC L.3, pgs.489 & 490 - Fnd 1/2" Iron Rod, used same wit as 1976 LCRC
3.) 1976-Kennedy, PS #17623; Survey L.003, pg 674 - Fnd 1/2" Iron Rod, used same wit as 1976 LCRC
4.) 1991-Bates, PS #16699; Survey L.009, pg.485 - Object found not stated, no witnesses
5.) 1981-Kennedy, PS #17623; Unrecorded Survey - Fnd 1/2" Iron Rod, used same wit as 1976 LCRC
6.) 1993-Kennedy, PS #17623; Unrecorded LCRC For M-10 Hadley Township - Fnd 1/2" Iron Rod
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1998-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod 1.0 feet below the road surface that is located in the centerline of Baldwin Road extending to the North & South, which has a gravel surface. The corner as recovered is on the range line. The East 1/4 corner of Section 25, T6N, R9E, Hadley Township (M-10) is located 18.59 feet to the North.

Witnesses from _____ were used to recover and verify the location of the found 1/2" Iron Rod.
I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

<u>A-10 to A-9</u> No GLO Survey recorded in Liber 009, page 485 = 2653.35 Ft. 2653.26 Ft. (MEA 1998)	<u>A-10 to M-10</u> No GLO 18.59 Ft. (m)
--	--

(Con't on back side of LCRC)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-10 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County
Remonumentation
S19°W 136.19' Set Mag Nail & Remon Washer SE face 18" Elm
S31°E 60.68' Set Mag Nail & Remon Washer SW face 27" Maple
N33°E 68.53' Set Mag Nail & Remon Washer NW face 28" Maple
N32°W 135.99' Set Mag Nail & Remon Washer NE face Power Pole
North 18.59 feet East 1/4 corner of Section 25, T6N, R9E, Hadley Township (M-10)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: Huston K. Kennedy Date 9-11-98
Surveyor's Michigan License No. 17623