

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

97 AUG 11 PM 2:29

For corners in

<u>Lapeer</u> (County)	Located In: <u>Metamora Township</u>	Corner Code # <u>D-5</u>
1. Public Land Survey	T <u>6N</u> R <u>10E</u>	<u>D-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Helen De Vaux
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 6/27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1822-GLO Wampler, D.S., Set Post 6" Ash S62°W 21 Links; 6" Lynn N06°E 17 Links
1.) 1979-Kay, PS #14096; Survey L.5, Pg.231 - Fnd ?
2.) 1988-Elrich, PS #18986; Unrecorded Survey - Fnd ?
3.) 1990-Kennedy, PS #17623; Unrecorded Survey - Fnd 1" Iron Rod in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1" Iron Rod in a Monument Box in the existing centerline of Lapeer Road (M-24 Highway) extending to the North & South, which has a bituminous surface over a concrete base. Also the existing centerline of Caley Road extending to the West, which has a gravel surface.

Witnesses from Unrecorded Survey #3 were used to recover and verify the location of the found 1" Iron Rod in a Monument Box.


I accepted the found 1" Iron Rod in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-5 I replaced the found 1" Iron Rod with a 1/2" x 18" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623 in a existing Monument Box
N86°W 93.42' Set PK & Remon Washer Top of Guard Rail Post
S73°W 93.08' Set PK & Remon Washer Top of Guard Rail Post
S87°E 23.84' Set PK & Remon Washer Top of Guard Rail Post
S47°W 52.30' Set PK & Remon Washer NW face Light Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 7623


Date 7-1-97



FIELD MEASUREMENTS BETWEEN

D-5 to D-4 No GLO, 2668.45 Ft. (MEA 1996), 2668.64 Ft. (MEA 1996)
D-5 to D-6 No GLO, 2618.15 Ft. (MEA 1996)

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY


RAY DAVIS P.S. CO. SURVEYOR
DATE 8-27-96

MISC D	6.00
REMLC	PD075
REMOVT	2.00