

SURVEY &
REMONUMENTATION

MAR 13 1998

SECTION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 AUG 11 PM 2:33

For corners in

Lapeer <small>(County)</small>	Located in: Metamora Township	Corner Code # D-9
1. Public Land Survey	T 6N R 10E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 6/27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

- 1822-GLO Wampler, D.S.; Set Post; 10" Tamarack N30°E 27 Links
- 1.) 1974-Henderson, PS #16043; LCRC L.2, Pg.563 - Fnd 3/4" Iron Bar
- 2.) 1972-Kennedy, PS #17623; Survey L.1, Pg.578 - Fnd ?
- 3.) 1973-Henderson, PS #16043; Survey L.2, Pg.122 - Fnd Re-rod
- 4.) 1974-Henderson, PS #16043; Survey L.2, Pg.664 - Fnd 3/4" Iron Bar, used same wit as 1974 LCRC
- 5.) 1975-Henderson, PS #16043; Survey L.3, Pg.402 - Fnd 3/4" Iron Bar, used same wit as 1974 LCRC
- 6.) 1977-Kay, PS #15096; Survey L.4, Pg.328 - Fnd 1" Bar
- 7.) 1981-Gravlin, PS #23510; Survey L.6, Pg.26 - Fnd 3/4" Iron Bar, used same wit as 1977 Survey
- 8.) Information received from the Lapeer County Road Commission - set or found Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996-Kennedy Survey, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in the existing centerline of Lapeer Road (M-24 Highway) extending to the North & South which has a bituminous surface over a concrete base. Brockler Road extending to the East & West, which has a gravel surface.

Witnesses from Surveys 6 & 7 were used to recover and verify the location of the found 5/8" Iron.

I accepted the found 5/8" Iron as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-9 I replaced the found 5/8" Iron Rod with a 1/2" x 18" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623 in a new Monument Box
- S19°E 122.21' Set PK & Remon. Washer West face Power Pole
- N60°E 64.42' Set PK & Remon. Washer NW face Power Pole
- N56°W 73.14' Set PK & Remon. Washer SW face Power Pole
- S17°W 68.20' Set PK & Remon. Washer Top of Guard Rail Post

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623


Date 7-1-97



LIBER 0005 PAGE 0430

FIELD MEASUREMENTS BETWEEN

D-9 to D-8 No GLO, 2643.36 Ft. (MEA 1996)
D-9 to D-10 No GLO, 2612.41 Ft. (MEA 1996)
N516416.0504, E 13405768.4285

DEEP GROUP
APPROVED LAND BORNER
PA 345 OF 1090
LADDER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 7-16-96

-ISSUED 11.00
REFILED 400.75
REMOVED 11.00