

SURVEY &  
REMONUMENTATION

MAR 13 1998

SECTION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
97 NOV 12 PM 3: 09

For corners in

Lapeer Located In: Corner Code #  
(County) Metamora Township

1. Public Land Survey T6N R10E D-10  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
1822-GLO Wampler D.S.; Post not set  
1.) 1973-Henderson, PS #16043; Survey L.2, Pg.122 - End Re-rod  
2.) 1990-Bates, PS #16699; Survey L.009, Pg.122 - Object not stated, no witnesses  
3.) 1969-Giffels-Webster Engineers, Inc.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996-Kennedy Survey, Inc. - Kennedy, P.S. #17623 - End P.K. Nail 0.85 feet West of the existing centerline of Lapeer Road (M-24 Highway) extending to the North & South, which has a bituminous surface over a concrete base with a fence-tree line extending to the West. Found second P.K. Nail 6.01 feet to the North.

I accepted the found P.K. Nail as the best evidence of the accepted corner position.

Field Measurements see back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
D-10 I replaced the found P.K. Nail with a 1/2" x 18" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation 17623 in a new Monument Box  
S24°W 141.68' Set PK & Remon. Washer SE face Power Pole  
S48°E 78.16' Set PK & Remon. Washer SW face 10" Elm  
N84°W 59.68' Set PK & Remon. Washer South face Power Pole  
S81°E 62.98' Set PK & Remon. Washer SW face 7" & 8" Elm North 6.01 feet found P.K. Nail

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the accepted corner.

Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date 7-17-97



LIBER 0005 PAGE 0476

FIELD MEASUREMENTS BETWEEN

D-10 = N 513800.0684, 13405885.6866


D-10 to D-9

No GLO  
GPS-MEA = 2618.61 Ft.

D-10 to D-11

No GLO  
Survey recorded in Liber 009, page 486 (6/15/90) = 2618.98 Ft.  
Unrecorded Survey by Giffels-Webster Engineering, Inc. (9/13/69) = 2619.30 Ft.  
GPS-MEA = 2618.98 Ft.

FREE GROUP  
APPROVED

  
RAY DAVIS S. L. SURVEYOR  
DATE 8-27-96  
9-29-97 New EVIDENCE