

MAY 28 1997

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 JAN 13 PM 2:41

For corners in

LAPEER

(County)

Located In:

Corner Code #/

1. Public Land Survey	T <u>6N</u> R <u>10E</u>	<u>L-1</u>
	T _____ R _____	_____
METAMORA TWP	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, HAROLD N. ELRICH, in a field survey on APRIL 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

JOSEPH WAMPLER SET 1/2 MILE POST - WHITE OAK 8" N 27° E 17 LINKS, WHITE OAK 4" S 56° W 27 LINKS
GILBERT BATES - STONE 25.15.9 - BRICK-SMALL STONES WHITE OAK 15" N 81° W 133 LINKS WHITE OAK 2 1/2" S 41° E 63 LINKS
1977 BERNARD HENDERSON P.S. #16043 (SURVEY) LIBER 004, PAGE 206 - FOUND 1/2" IRON ROD N 45° E 38.40 FEET 30" OAK, N 50° W 29.10 FEET 14" LOCUST, S 40° E 28.46 FEET 18" LOCUST, S 15° W 35.04 FEET 36" OAK
1980 LELAND D. BATES P.S. #16699 (SURVEY) LIBER 006, PAGE 128 & 129 - N 45° E 38.40 FEET 30" OAK, N 50° W 29.10 FEET 14" LOCUST, S 15° W 35.04 FEET 36" OAK

(SEE BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 HAROLD N. ELRICH P.S. #18986 - FOUND 1/2" IRON IN CENTERLINE OF SUTTON ROAD, STRAIGHT, WITH TREE LINE AND FENCE RUNNING TO SOUTH. FOUND THREE WITNESSES FROM PREVIOUS SURVEYS THAT LOCATE 1/2" IRON FOUND. IRON TWO FEET SOUTH OF CENTERLINE.

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF ORIGINAL POSITION OF NORTH 1/4 CORNER OF SECTION 1, T6N-R10E, METAMORA TOWNSHIP, LAPEER COUNTY, MICHIGAN

MEASURED REFERENCES - L-1 TO K-1 2626.35 FEET
L-1 TO M-1 2737.62 FEET

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

RAY DAVIS S. CO. SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 8-27-96

L-1 PLACED LAPEER COUNTY REMONUMENTATION CAP ON 1/2" IRON FOUND

SET NEW WITNESSES - N 50° W 29.10 FEET P.K. NAIL & WASHER IN 14" LOCUST
N 45° E 38.34 FEET P.K. NAIL & WASHER IN 34" OAK
S 70° E 63.07 FEET P.K. NAIL & WASHER IN 12" OAK
S 35° W 26.32 FEET P.K. NAIL & WAHSER IN 12" LOCUST

Signed by Harold N. Elrich
Surveyor's Michigan License No. _____



Date Dec 17, 1996

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

1980 LELAND D. BATES P.S. #16699 (LAND CORNER RECORDATION CERTIFICATE)
LIBER 004, PAGE 21, FOUND IRON N 45° E 38.40 FEET 30" OAK,
N 50° W 29.10 FEET 14" LOCUST, S 15° W 35.04 FEET 36" OAK

1984 HAROLD N. ELRICH P.S. #18986 (SURVEY) FOUND 1/2" IRON
N 45° E 38.40 FEET 30" OAK, N 50° W 29.10 FEET 14" LOCUST,
S 40° E 28.46 FEET 18" LOCUST, S 15° W 35.04 FEET 36" OAK

MISC D	9.00
REMLC	P0075
REMON	2.00