

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

98 FEB 18 PM 2:50

For corners in

Lapeer
(County)

Located in: Metamora Corner Code #
Township

- | | | | |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>6N</u> | R <u>10E</u> | <u>M-4</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy a field survey on 08/15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S., Set Post 23" Birch N40°W 40 Links
1.) 1989-Tietsema, PS #20712; Unrecorded Survey - Fnd 1/2" Iron Rod
2.) 1989-Carlson, PS #9189; Unrecorded Survey - Fnd 1/2" Re-rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod .70 feet below the surface, 3.00 feet West of the existing centerline of Thornville Road extending to the North & South, which has a gravel surface. The West 1/4 corner of Section 7, T6N, R11E, Dryden Township (A-4) is located 154.18 feet to the North.

Witnesses from unrecorded Surveys #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation M-4
N51°W 33.09' Set PK & Remon Washer NW face 24" Oak
S89°E 36.34' Set PK & Remon Washer South face 16" Elm
S26°E 63.84' Set PK & Remon Washer South face 9" Poplar
N34°W 31.80' Set PK & Remon Washer NE face 10' Walnut
North 154.18 feet West 1/4 corner of Section 7, T6N, R11E, Dryden Township (A-4)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Huston K. Kennedy
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 17623

Date 12-31-97



SURVEY &
REMONUMENTATION

MAR 13 1998

LIBER0006 PAGE0016

SECTION

PEER GROUP
APPROVED THIS CORNER

FIELD MEASUREMENTS BETWEEN

M-4 to A-3

No GLO
GROUND-MEA = 154.18 Ft.

M-4 to A-4

No GLO
GROUND-MEA = 154.18 Ft.

M-4 to M-3

GLO = 40 chains or 2640.00 Ft.
Unrecorded Survey by McAlpine, PS #1015 (May 1950) = 2716.55 Ft.
GROUND-MEA = 2715.79 Ft.

M-4 to M-5

GLO = 40 chains or 2640.00 Ft.
Unrecorded Survey by McAlpine, PS #1015 (May 1950) = 2426.72 Ft.
GROUND-MEA = 2421.72 Ft.

[Handwritten Signature]
DATE 9-29-97

LIBER
PAGE