

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 JAN 11 PM 2:19

LIBER-NO. 05 PAGE NO. 213
Helen De Vough
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

For corners in
Lapeer
County

Located In: Metamora Twp. Corner Code M-5

1. Public Land Survey	T	6N	R	10E	M-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

PEER GROUP
APPROVED LAND CORNER
P.A. 74 OF 1970
LAPEER COUNTY

I, Huston K. Kennedy, in a field survey on December 31, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

- 1822-GLO Wampler, D.S.; Set Post; 4" Aspen S43°E 38 Links
- 1975-Kay, P.S. #14096; Survey L.003, Pg.473 - Fnd 1" Angle Iron (Metamora Twp.)
 - 1976-Henderson, P.S. #16043; Survey L.003, Pg.800 - Fnd Angle Iron (Dryden Twp.)
 - 1979-Elrich, P.S. #18986; Survey L.005, Pg.324 - Fnd 1/2" Angle Iron (Metamora Twp.)
 - 1980-Elrich, P.S. #18986; Survey L.005, Pg.736 - Fnd Iron, used same wit as third Survey (Metamora Twp.)
 - 1984-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Iron Pipe (Metamora Twp.)

RAY DAVIS P.S. CO. SURVEYOR
DATE 1-11-95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd Angle Iron with a P.K. Nail in the centerline of Dryden Road to the East & West, which has a bituminous surface, and Thornville Road to the North & South, which has a gravel surface. This corner is also being accepted and being used as a common corner with the Northwest corner of Section 18, and the Southwest corner of Section 7, T6N, R11E, Dryden Township.

Witnesses from Recorded Survey #1, 2 & 3 were used to recover and verify the location of the found Angle Iron with a P.K. Nail

I accept the found Angle Iron with a P.K. Nail as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 I replaced the found Angle Iron with a P.K. Nail with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623 A-5 & M-5 in a new Monument Box.
- S32°W 50.48' Set Nail & Remon. Washer NW face Power Pole
 - S49°E 59.20' Set Nail & Remon. Washer NE face Power Pole
 - N41°E 55.50' Set Nail & Remon. Washer NW face Power Pole
 - N36°W 59.30' Set Nail & Remon. Washer NE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy Date January 9, 1995
Surveyor's Michigan License No. 17623

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1992

LIBER 0005 PAGE 0213