

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6</u> N R <u>10</u> E	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

93 DEC 30 AM 10:18

LIBER NO 5 FILE NO. 50

Melissa Miles
REGISTERED DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Wampler, D.S.; Set Post; 20" White Oak N 64°W 41 lks, 5" ? S 38°E 29 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a concrete monument that appears to be a common corner for Sections 25 and 36 in Metamora Township and Sections 30 and 31 in Dryden Township. This is based upon unrecorded surveys by Carl H. Carlson, P.S. #9189, and Glenn J. Heil, P.S. #18993. Carlson surveyed the SW Cor Sec. 30, Dryden Township and found a concrete monument. Heil surveyed the NE Cor. Sec 36, Metamora Township and found a concrete monument.

Based upon the unrecorded surveys the concrete monument is accepted as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 A Concrete Monument
Due North-30.48'-P.K. Nail w/washer in West face 33" Oak
Due West-20.60'-P.K. Nail w/washer in North face 8" Maple
S44°W-28.56'-P.K. Nail w/washer in NW face 27" Bass
S61°E-34.59'-P.K. Nail w/washer in NE face 39" Oak
N15°E-15.83'-P.K. Nail w/washer in West face 9" Ash



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date 11/24/93