

1993

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in

LAPEER (County)

Located In:

Corner Code #

- 1. Public Land Survey T 6 N R 10 E M-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

93 DEC 30 AM 10:20

LIBER NO 5 FILE NO 52 Melissa Miles REGISTERED SURVEYOR LAPEER MICHIGAN

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

Huston K. Kennedy in a field survey on December 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Wampler, D.S.; Set post; 10" White Oak N 77°W 27 lks, 13" White Oak S 86°E 20 lks 1981 Elrich, P.S. #18986; LCRC L.3, Pg.610; Fnd concrete monument 1981 Elrich, P.S.#18986; Survey L.5, Pg.948; Fnd concrete monument; Same wits as 1981 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd concrete monument in the center of Hempstead Road to the North, and the center of Davison Lake Road to the west. Both roads are gravel. Found 2 previous witnesses existing and used them to recover the found concrete monument. The monument is located East of the travelled road because the road curves at the intersection of Davison Lake Road and Hempstead Road.

I accepted the found concrete monument as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 a concrete monument N57°W 51.40' Set nail w/remon. tag above existing witness in SW face 7" Ash N44°E 22.98' Set nail w/remon. tag above existing witness in SE face 13" & 19" Twin Bass S70°W 47.92' Set nail w/remon. tag in N. face 9" Cherry S63°E 34.51' Set nail w/remon. tag above existing witness in SW face 15" & 18" Twin Oak N87°E 30.07' Set nail w/remon. tag in N. face Power Pole



Signed by [Signature]

Date 11/20/93

Surveyor's Michigan License No. 17623