

SURVEY & REMONUMENTATION

MAR 13 1998

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
97 NOV 12 PM 2:58

For corners in

Lapeer

(County)

Located In:

Dryden Township

Corner Code #

- 1. Public Land Survey      T 6N R 11E      A-2
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- 2. Property Controlling    S    T    R                    \_\_\_\_\_
- in Section                S    T    R                    \_\_\_\_\_
- 3. Miscellaneous            S    T    R                    \_\_\_\_\_
- Property in Sec.         S    T    R                    \_\_\_\_\_

Melissa De Vaux  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 8/15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6												
3													
4	7												
5													
6	16												
7													
8	19												
9													
10	30												
11													
12	31												
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S., No post was set
- 1.) 1976-Kobs, PS #14097; LCRC L.3, pg.259 - Fnd 1/2" Iron Bar.
- 2.) 1976-Kobs, PS #14097; Survey L.3, pg.837 - Fnd 1/2" Iron Bar, used same wit as 1976 LCRC
- 3.) 1976-Kobs, PS #14097; Survey L.3, pg.841 - Fnd 1/2" Iron Bar, used same wit as 1976 LCRC
- 4.) 1977-Elrich, PS #18986; Survey L.4, pg.221 - Fnd 1/2" Iron, used same wit as 1976 LCRC
- 5.) 1988-Elrich, PS #18986; Survey L.8, pg.41 - Fnd 1/2" Iron, used same wit as 1976 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod .75 feet below the surface and in the existing centerline of Thornville Road extending to the North & South, which has a gravel surface. A fence-rock row extending to the East & West, and 15.00 feet North of the center of driveway for house #3270.

Witnesses from LCRC #1 & Survey #5 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

Field Measurements between see back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-2 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation A-2
- S77°E 30.18' Set PK & Remon Washer SW face 23" Oak      Due East 32.50 feet, found 1/2" Iron Rod
- S32°E 61.48' Set PK & Remon Washer SW face 18" Oak      Due West 33.10 feet, found 1/2" Iron Rod
- S33°W 68.23' Set PK & Remon Washer SE face 27" Twin Oak
- N76°W 31.42' Set PK & Remon Washer North face 10' Sassafras

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date 9/30/97

LIBER 0005 PAGE 0456

FIELD MEASUREMENTS BETWEEN

A-2 to A-2

GLO = 46 chains or 3036.00 Ft.  
Survey recorded in Liber 4, page 221 = 2836.63 Ft.  
GROUND-MEA = 2836.94 Ft.

A-2 to A-3

No GLO  
Survey recorded in Liber 3, page 837 = 2661.50 Ft.  
Survey recorded in Liber 3, page 841 = 2661.50 Ft.  
Survey recorded in Liber 8, page 41 = 2661.50 Ft.  
GROUND-MEA = 2661.71 Ft.

A-2 to M-2

No GLO  
Common Corner

DEED GROUP  
RECORDED IN THE PUBLIC RECORDS  
OF THE COUNTY OF...  
STATE OF...  
DATE 9-29-97