

SURVEY &
REMONUMENTATION

MAR 13 1998

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
97 NOV 12 PM 3:00

For corners in

| | | |
|------------------------------------|---|---------------|
| Lapeer | Located in: | Corner Code # |
| (County) | Dryden Township | |
| 1. Public Land Survey | T <u>6N</u> R <u>11E</u> | <u>A-4</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 8/15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S., No post was set
1.) 1987-Elrich, PS #18986; Survey L.7, pg.520 - Fnd a Iron Rod
2.) 1990-Elrich, PS #18986; Survey L.8, pg.642 - Object found not stated, no witnesses
3.) 1996-Elrich, PS #18986; Survey L.11, pg.562 - Fnd a Iron Rod, used same wit as 1987 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 1.10 feet below the surface, and 3.60 feet West of the existing centerline or Thornville Road extending to the North & South, which has a gravel surface. The East 1/4 corner of Section 12, T6N, R10E, Metamora Township (M-4) is located 154.18 feet to the South.

Witnesses from _____ were used to recover and verify the location of the found 1/2" Iron Rod.
I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

Field Measurements between see back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-4 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation A-4
N31°W 45.39' Set PK & Remon Washer NE face 12" Oak East 33.02 feet, found 1/2" Iron Rod
S82°W 44.22' Set PK & Remon Washer North face 19" Walnut
S76°E 43.60' Set PK & Remon Washer SW face 14" Poplar
N39°E 76.78' Set PK & Remon Washer NW face 10" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 17623

Date 9-30-97



FIELD MEASUREMENTS BETWEEN

A-4 to A-3

No GLO
Survey recorded in Liber 007, page 520 = 2561.69 Ft.
Survey recorded in Liber 11, page 562 = 2561.69 Ft.
GROUND-MEA = 2561.62 Ft.

A-4 to A-5

No GLO
Survey recorded in Liber 8, page 642 = 1806.08 Ft.
GROUND-MEA = 2575.90 Ft.

A-4 to M-4

No GLO
GROUND-MEA = 154.18 Ft.

TEEP GROUP
APPROVED LAND CORNER
PA 345 OF 1990

WYOMING COUNTY

[Signature]
DAY WAYS & SONS, INC. ENGINEER
DATE 9-29-97