

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lapeer
(County)

Located in: Dryden
Twp.

Corner Code #
A-6

1. Public Land Survey	T <u>6N</u> R <u>11E</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
94 NOV 30 AM 8:19
LIBER NO. 65 PAGE NO. 122
Holmes & Naught
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1822-GLO Wampler, D.S.; Set Post; 14" White Oak S63*W 38 Links; 23" White Oak S85*E 50 Links
 - 1.) 1979-Henderson, P.S. #16043; Survey L.005, Pg.314 - Fnd 1/2" Iron
 - 2.) 1981-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
[Signature]
RAY DAVIS P.S. CO. SURVEYOR
DATE 11-29-94

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 4' East of the centerline of Thornville Road, which has a gravel surface, fence and tree row extending to the East, and a pond to the West. I made a survey of the East 1/2 of Section 13, T6N, R10E, an accepted the West 1/4 corner of Section 18, T6N, R11E, as a common corner with the East 1/4 corner of Section 13, T6N, R10E.

Witnesses from Survey #1 were used to recover and verify the location of the found 1/2" Iron Rod.
I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-6 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623.
M-6 & A-6
S43°W 49.59' Set PK & Remon. Washer SE face 11" Cherry
N15°E 50.17' Set PK & Remon. Washer West face 10" Bean Hoop
N61°W 41.17' Set PK & Remon. Washer NE face 12" Oak
N81°W 35.29' Set PK & Remon. Washer North face 15" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *[Signature]*
Surveyor's Michigan License No. 17623

Date October 14, 1994

LIBER 0005 PAGE 0123

