

SURVEY &  
REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

| For corners in                        | Lapeer<br>(County) | Located in | Dryden<br>Twp. | Corner Code # |
|---------------------------------------|--------------------|------------|----------------|---------------|
| 1. Public Land Survey                 |                    | T 6N       | R 11E          | A-8           |
|                                       |                    | T          | R              |               |
|                                       |                    | T          | R              |               |
|                                       |                    | T          | R              |               |
| 2. Property Controlling<br>in Section | S                  | T          | R              |               |
|                                       | S                  | T          | R              |               |
| 3. Miscellaneous<br>Property in Sec.  | S                  | T          | R              |               |
|                                       | S                  | T          | R              |               |

94 NOV 30 AM 8:22  
LIBER NO. 05 PAGE NO. 125  
Melissa DeVaugh  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  |    |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 6  | 5  | 4  | 3  | 2  |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Huston K. Kennedy in a field survey on June 15, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 5" Aspen N67°E 14 Links; 9" Elm S67°W 31 Links  
1.) 1974-Elrich, P.S. #18986; LCRC L. 002, Pg.595 - Fnd 1" Iron  
2.) 1980-Elrich, P.S. #18986; Survey L.005, Pg.525 - Fnd 1" Iron, used same wit as 1974 LCRC  
3.) 1980-Kennedy, P.S. #17623; Unrecorded Survey - Fnd "I" Iron

PEER GROUP  
APPROVED LAND CORNER  
PA 845 OF 1990  
LAPEER COUNTY.  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 11-29-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe 4" deep in centerline of Thornville Road to the North, which has a gravel surface and 7' South of the centerline of Casey Road to the East & West, which has a gravel surface. A second 1/2" Iron Rod was found 1.55' Southwest. The East 1/4 corner of Section 24, T6N, R10E, is being accepted and used as a common corner with the West 1/4 corner of Section 19, T6N, R11E.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1" Iron Pipe.


I accepted the found 1/2" Iron Pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-8 I replaced the found 1" Iron Pipe with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Lapeer County Remonumentation #17623.  
M-8 & A-8  
N16°E 99.48' Set PK & Remon. Washer NW face Power Pole  
S52°E 91.83' Set PK & Remon. Washer NE face 9" Elm  
S21°E 64.09' Set PK & Remon. Washer SW face Power Pole  
S63°W 35.40' Set PK & Remon. Washer NW face 15" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date October 14, 1994  
Surveyor's Michigan License No. 17623



LIBER 0005 PAGE 0125

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1991  
REVISED MAY 14, 1979  
REVISED JAN. 1982