

MAR 13 1998

SECTION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 NOV 12 PM 3: 05

For corners in

<u>Lapeer</u> (County)	Located In: Dryden Township	Corner Code # A-13
1. Public Land Survey	T <u>6N</u> R <u>11E</u>	<u>A-13</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 8/15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S., Set Post 10" White Oak N77°W 27 Links; 18" White Oak S86°E 20 Links  
 1.) 1994-Anticliff, PS #25826; LCRC L.14833, pg.157 (Oakland County) - Fnd a 4" Concrete Monument  
 2.) 1993-Kennedy, PS #17623; Unrecorded LCRC - Fnd a Concrete Monument  
 3.) 1981-Elrich, PS #18986; Survey L.5, pg.948 - Fnd a Concrete Monument  
 4.) 1990-Elrich, PS #18986; Survey L.8, pg.690 - Fnd a Concrete Monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 4" diameter Concrete Monument with 2" diameter brass cap stamped Oakland County Remonumentation, PS #25826 in the intersection of the centerline of Davison Lake Road extending to the West, which has a gravel surface, and Hampsted Road extending to the North, which has a gravel surface. This corner is being accepted and used as a common corner with the Southeast corner of Section 36, T6N, R10E, Metamora Township (M-13), Northeast corner of Section 1, T5N, R10E, Oxford Township (M-1) and Northwest corner of Section 6, T5N, R11E, Addison Township (A-1).

Witnesses from LCRC #1, 2, Surveys #3 & 4 were used to recover and verify the location of the found 4" diameter Concrete Monument with 2" diameter brass cap stamped Oakland County Remonumentation, PS #25826.

I accepted the found 4" diameter Concrete Monument with 2" diameter brass cap stamped Oakland County Remonumentation, PS #25826 as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-13 I accepted the found 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #25826  
 N57°E 33.66' Fnd PK Nail & Oakland County Remon Washer SE face 18" Oak  
 N05°W 90.98' Fnd PK Nail & Oakland County Remon Washer East face 10" Ash  
 N50°W 68.97' Fnd PK Nail & Oakland County Remon Washer North face 12" Cherry  
 Due East 29.98' Fnd PK Nail & Oakland County Remon Washer South face Utility Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date 9-30-97

PEER GROUP  
APPROVED LIND CORNER

*[Handwritten signature]*

DATE 9-29-97

FIELD MEASUREMENTS BETWEEN

A-13 to A-12

No GLO

Survey recorded in Liber 005, page 948 = 2658.57 Ft. (M-12 to M-13)

GROUND-MEA = 2658.68 Ft. (A-12 to M-13)

FILE NO  
70073  
FILE