

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lapeer
(County)

Located In:
DRYDEN TWP

Corner Code #

- 1. Public Land Survey T 6N R 11E K-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Shelby W Money, in a field survey on October 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1816-GLO Wampler, Set a Post on twp line to the north.
1. L1, Pg 452, May 1972 survey by Henderson Bates, Found 1/2" iron.
 2. L2, Pg 879, August 1974 survey by Henderson Bates, Found 1/2" iron.
 3. L3, Pg 234 April 1975 survey by Kay Engineering, Found 1/2" iron.
 4. L4, Pg 331 October 1977 survey by Kay Engineering, Found 1/2" iron.
 5. L5, Pg 240 October 1978 survey by Kay Engineering, Found 1/2" iron.
 6. L5, Pg 248 September 1978 survey by Kay Engineering, Found 1/2" iron.
 7. L5, Pg 330 October 1978 survey by Kay Engineering, Found 1/2" iron.
 8. L5, Pg 668 March 1979 survey by Kay Engineering, Found 1/2" iron.
 9. L6, Pg 248 September 1982 survey by Henderson Bates, Found 1/2" iron.
 10. L1, Pg 183, April 1972 LCRC by Harold Elrich, Found 1/2" iron.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 1/2" iron 2 ft north of the physical centerline of Sutton Road, which has a gravel surface and runs east and west and at intersection of Mill Road which extends to the south and has an asphalt surface. Found corner is 2.46 feet north of Town Line. The following witnesses from the LCRC were used to locate the corner:
1. N 75° E 50.65' Nail & Tag 12" Cherry. Measured 50.68'
 2. N 80° W 33.05' Nail & Tag T.P. Measured 32.83'


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K1 Placed 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092 on found 1/2" iron,
1. Az 70° 50.68' to 60 p nail found in northwest face of a 20" cherry.
 2. Az 150° 104.95' to P. K. nail found in west face of a 12" scotch pine.
 3. Az 230° 41.08' to P. K. nail found in northwest face of a utility pole.
 4. Az 305° 32.83' to nail & tag found in southeast face of a utility pole.
 5. Az 335° 68.66' to P. K. & Lapeer County Remon Tag set in the northeast face of a utility pole

FIELD MEASUREMENTS
K-1 TO K-2 2844.50' GLO 2874.96' K-1 TO J-13 (T7N, R11E) 873.22 GLO 97.02'

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Shelby W Money
Surveyor's Michigan License No. 30092

Date 12/22/98



RECEIVED FOR RECORD
99 JAN -6 PM 1:03

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

430

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1890
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 10-13-98