

MAR 29 1999

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER
(County)

Located In:
DRYDEN TWP

Corner Code#

- 1. Public Land Survey T6N R11E L-1
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

RECEIVED FOR RECORD

99 JAN -6 PM 1:19

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

433

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Shelby W Money, in a field survey on October 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

PEER GROUP
PA 345 OF 1990
LAPEER COUNTY
[Signature]
RAY DAVIS P.S. CO. SURVEYOR
DATE 10-13-98

Township line surveyed in 1816 by Wampler for T7N, R11E Attica Twp. No 1/2 mile post for section 1 of Dryden Twp being set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Set corner at half distance from K-1 to M-1 on line between K-13 and L-13 of Attica Twp.

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Set a 1/2" iron with a 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092.

- 1. Az 80° 68.74' to P. K. & Lapeer County Remon Tag set in the south face of a 8" maple.
- 2. Az 110° 97.83' to P. K. & Lapeer County Remon Tag set in the north face of a utility pole.
- 3. Az 250° 59.35' to P. K. & Lapeer County Remon Tag set in the northwest face of a utility pole.
- 4. Az 285° 75.87' to P. K. & Lapeer County Remon Tag set in the west face of a 28" ash.

FIELD MEASUREMENTS
West to K-13 Attica Twp. 1826.53' Measure
East to L-13 Attica Twp. 791.89' Measure

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST BEST POSITION FOR THE CORNER.

Signed by *[Signature]* Date 12/20/96
Surveyor's Michigan License No. 30092

