

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 27 PM 1:09

For corners in

<u>LAPEER</u> (County)	Located In: DRYDEN TOWNSHIP	Corner Code # <u>M-4</u>
1. Public Land Survey	T <u>6N</u> R <u>11E</u>	<u>M-4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Melissa DeLoach
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William E. Soderberg, in a field survey on MAY 7, 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. GLO None for this corner
2. 2-28-86 Survey recorded by Herbert Kobs 14097 in liber 7, page 416 Found 1/2" Iron
3. 3-20-87 Survey recorded by Herbert Kobs 14097 in liber 7, page 695 Found 1/2" Iron
4. 3-20-89 Survey recorded by Donald King 30085 in liber 8, page 532 Found 1/2" Iron
5. 12-10-90 Survey recorded by Earl Gravlin 23510 in liber 9, page 78 Found 1/2" Iron
6. 12-12-90 Survey recorded by Harold Elrich 18986 in liber 9, page 234 Found 1/2" Iron
7. 12-9-92 Survey recorded by Earl Gravlin 23510 in liber 9, page 947 Found 1/2" Iron
8. 1-12-94 Survey recorded by Earl Gravlin 23510 in liber 10, page 442 Found 1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: DATE

Found 1/2" Rebar on centerline Bishop Road. (Gravel). No occupation to the West.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
Ray Davis
RAY DAVIS, P.E. CO. SURVEYOR
DATE 7-16-96

Witness found for the corner from items 2, 3, 4, 5, 6, 7 and 8

- West 22.47' Found PK in Anchor post
- NW 24.37' Found PK in 6" Ash
- NE 37.76' Found PK in 14" Tree
- South 51.36' to A-4 Almont Township as called for on Recorded Survey liber 9, page 254.

Measured: North to M-3 Dryden Township GLO 40 chs or 2640 feet; 2634.23 feet Graclin L10, P 442; 2634.10 feet measured
South to M-5 Dryden GLO 40 chs or 2640 feet; 2644.92 feet Kobs, King, Elrich and Gravlin; 2644.92 feet measured.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed Lapeer County Remonumentation cap stamped M 4 17635 on found 1/2" rebar

- AZ 60° 37.73' Set PK with Lapeer County tag in NW face 18" Ash
- AZ 85° 25.17' Set PK with Lapeer County tag in S face 8" Ash
- AZ 270° 22.48' Found PK, set PK with Lapeer County tag in N face Anchor post
- AZ 330° 24.39' Set PK with Lapeer County tag in NE face 10" Ash
- AZ 270° 33.00' Found Iron with cap 23510
- AZ 180° 51.36' Found A-4 Almont Township

Signed by William E. Soderberg Date 12-19-96

Surveyor's Michigan License No. 17635

