

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 27 PM 1:10

**COMMISSION**

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
	<u>DRYDEN TOWNSHIP</u>	
1. Public Land Survey	<u>T 6N R 11E</u>	<u>M-5</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William E. Soderberg, in a field survey on MAY 7, 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1816 GLO Joseph Wampler Set post No witnesses found
  - 10-31-72 LCRC recorded by Bernard Henderson 16043 in liber 2, page 21 Set PK nail
  - 10-31-72 Survey recorded by Bernard Henderson 16.43 in liber 1, page 761 Set PK nail
  - 3-23-74 Survey recorded by Robert Kay 14097 in liber 2, page 683 Found unknown
  - 10-27-75 Survey recorded by Herbert Kobs 14097 in liber 3, page 498 Found PK nail
  - 7-24-79 Survey recorded by Charles Getz 25843 in liber 5, page 607 Found unknown
  - 8-21-80 Survey recorded by Harold Elrich 18986 in liber 5, page 850 Found PK nail
  - 2-28-86 Survey recorded by Herbert Kobs 14097 in liber 7, page 416 Found PK nail
  - 3-5-87 Survey recorded by Harold Elrich 18986 in liber 7, page 591 Found PK nail
  - 8-4-87 Survey recorded by Harold Elrich 18986 in liber 7, page 615 Found PK nail
  - 3-20-87 Survey recorded by Herbert Kobs 14097 in liber 7, page 695 Found PK nail
  - 1-27-88 Survey recorded by Harold Elrich 18986 in liber 7, page 809 Found PK nail
  - 9-23-88 Survey recorded by Earl Gravin 23510 in liber 8, page 79 Found PK nail
  - 3-20-89 Survey recorded by Donald King 30085 in liber 8, page 532 Found PK nail
  - 10-12-89 Survey recorded by Harold Elrich 18986 in liber 8, page 587 Found 1/2" Iron in monument box
  - 10-12-90 Survey recorded by Harold Elrich 18986 in liber 9, page 234 Found 1/2" Iron in monument box
  - 12-9-92 Survey recorded by Earl Gravin 23510 in liber 9, page 947 Found 1/2" Iron
  - 9-18-92 Survey recorded by Donald King 30085 in liber 10, page 182 Found 1/2" Iron in monument box

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS S. CO. SURVEYOR  
7-16-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" Rebar IN monument box in asphalt apron for Dryden road on centerline Bishop Road. Line up with centerline of Dryden Road to the West.

No witness found for the corner.

Measured: South to M-6 Dryden Township GLO 40 chs or 2640 feet; 2547.31 feet Getz L5, P 607; 2547.44 feet measured  
North to M-4 Dryden GLO 40 chs or 2640 feet; 2644.92 feet Kobs, King, Elrich and Gravin; 2644.92 feet measured.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed Lapeer County Remonumentation cap stamped M 5 17635 on found 1/2" rebar

- |         |         |   |
|---------|---------|---|
| AZ 40°  | 47.19'  | Set PK with Lapeer County tag in NW face utility pole |
| AZ 160° | 90.50'  | Set PK with Lapeer County tag in W face 24" Willow    |
| AZ 260° | 159.91' | Set PK with Lapeer County tag in N face utility pole  |
| AZ 320° | 50.30'  | Set PK with Lapeer County tag in NE face utility pole |

Signed by William E. Soderberg Date 12-29-96  
Surveyor's Michigan License No. 17635

