

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u>	Located In:	Corner Code #
(County)	DRYDEN TOWNSHIP	
1. Public Land Survey	T <u>6N</u> R <u>11E</u>	<u>M-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD

94 DEC -9 PM 3:16
 LIBER NO. 005 STAGE NO. 142
Melissa DeLoach
 REGISTER OF DEEDS
 LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on MAY 19, 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	20	19	18	17	16	15	14	13	12	11	10	9
11												
12	31	30	29	28	27	26	25	24	23	22	21	20
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1816)	PAGE 348	JOSEPH WAMPLER	NO WITNESSES FOUND
SURVEY (1975) LIBER 0003	PAGE 522	HAROLD N. ELRICH, P.S. #18986	FOUND 1/2" IRON
SURVEY (1979) LIBER 0005	PAGE 607	CHARLES S. GETZ, P.S. #25043	UNKNOWN
SURVEY (1980) LIBER 0005	PAGE 850	HAROLD N. ELRICH, P.S. #18986	FOUND 1/2" IRON
SURVEY (1988) LIBER 0008	PAGE 079	EARL E. GRAVLIN, P.S. #23510	UNKNOWN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REBAR IN GRAVEL ROAD

SURVEY (1980) LIBER 0005 PAGE 850 S 70W 29.50' 10" ASH
 WEST 33.00' 1/2" IRON

M-6 TO M-5 T.7N., T.11E. MEASURED 2547.44'
 M-6 TO M-7 T.7N., T.11E. MEASURED 2548.20'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1/2" REBAR AND REPLACED WITH
 BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-6 ON A 1/2" X 18" REBAR

AZIMUTH 187° 103.23' FOUND, THE WEST 1/4 POST SECTION 18 OF T.6N., R.12E.; (A-6 / ALMONT TOWNSHIP)
 AZIMUTH 100° 25.07' SET, PK W/TAG #30092 IN THE SOUTH FACE OF A 24" LOCUST
 AZIMUTH 260° 29.87' SET, PK W/TAG #30092 IN THE SOUTH FACE OF A 10" ASH
 AZIMUTH 270° 33.00' FOUND, AN OLD 1/2" REBAR
 AZIMUTH 205° 69.51' SET, PK W/TAG #30092 IN THE EAST FACE OF AN 8" ASH
 AZIMUTH 187° 103.28' FOUND, 1/2" REROD W/CAP #30992, A-6 / T.6N., R.12E., ALMONT TOWNSHIP

PEER GROUP
APPROVED LAND CORNER
 PA 345 OF 1990
 LAPEER COUNTY

Signed by *Shelby W. Money* Date DECEMBER 2, 1994

Surveyor's Michigan License No. 30092 BAY DAVIS P.S. CO. SURVEYOR

DATE 12-2-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1982

LIBER 0005 PAGE 0142