

SURVEY &
REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located in:	Corner Code #
	DRYDEN TOWNSHIP	
1. Public Land Survey	T. <u>6N</u> R. <u>11E</u>	<u>M-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Property Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Sec.	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____

RECEIVED FOR RECORD

94 DEC -9 PM 3:15

LIBER NO. 05 PAGE 141

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on MAY 19, 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


G.L.O. (1816)	PAGE 348	JOSEPH WAMPLER	NO WITNESSES FOUND
G.L.O. (1816)	PAGE 558	JOSEPH WAMPLER	NO WITNESSES FOUND
SURVEY (1972) LIBER 0001	PAGE 496	LELAND D. BATES, P.S. #16699	FOUND 1/2" ROD
LCRC (1972) LIBER 0001	PAGE 415	LELAND D. BATES, P.S. #16699	FOUND 1/2" ROD
WITNESS (1983) UNRECORDED		LAPEER COUNTY ROAD COMMISSION	FOUND 1/2" IRON
SURVEY (1973) LIBER 0002	PAGE 253	BERNARD HENDERSON, P.S. #16043	FOUND 1/2" ROD
SURVEY (1976) LIBER 0003	PAGE 522	HAROLD N. ELRICH, P.S. #18966	FOUND 3/8" IRON
SURVEY (1976) LIBER 0003	PAGE 532	HAROLD N. ELRICH, P.S. #18966	FOUND 1/2" IRON
SURVEY (1976) LIBER 0003	PAGE 823	HAROLD N. ELRICH, P.S. #18966	FOUND 3/8" IRON
SURVEY (1977) LIBER 0004	PAGE 086	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR
SURVEY (1978) LIBER 0004	PAGE 457	HAROLD N. ELRICH, P.S. #18966	FOUND 3/8" IRON
SURVEY (1979) LIBER 0005	PAGE 443	HAROLD N. ELRICH, P.S. #18966	FOUND 1/2" IRON
SURVEY (1980) LIBER 0005	PAGE 607	CHARLES S. GETZ, P.S. #25043	FOUND 5/8" IRON
WITNESS (1988) UNRECORDED		LAPEER COUNTY ROAD COMMISSION	FOUND 1/2" IRON
SURVEY (1990) LIBER 0008	PAGE 994	JAMES THOMAS BAILEY, P.S. #33968	FOUND 1/2" ROD
SURVEY (1991) LIBER 0009	PAGE 361	JAMES THOMAS BAILEY, P.S. #33968	FOUND 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REBAR IN GRAVEL ROAD
FOUND LARGE STUMP TO WEST AT 29± AND FENCE LINE TO WEST
LIBER 0008 PAGE 994 WEST 33.00' CAPPED IRON RLS #14097
M-7 TO M-6 T.7N., T.11E. MEASURED 2548.20'
M-7 TO M-8 T.7N., T.11E. MEASURED 2541.09'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1/2" REBAR SET BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-7
AZIMUTH 187° 156.92' FOUND, 1/2" REBAR; CORNER # A-7 OF T.6N., R.12E. (ALMONT TOWNSHIP); LAPEER CTY
AZIMUTH 350° 208.20' SET, PK W/LAPEER REMONUMENTATION TAG IN NORTHEAST FACE OF UTILITY POLE
AZIMUTH 210° 214.80' SET, PK W/LAPEER REMONUMENTATION TAG IN SOUTHEAST OF GT BOX POLE
AZIMUTH 270° 120.10' SET, PK W/LAPEER REMONUMENTATION TAG IN SOUTH FACE OF 12' LOCUST CLUMP
AZIMUTH 270° 33.70' FOUND, 1/2" REBAR; A-7 / T.6N., R.12E., ALMONT TOWNSHIP



PEER GROUP
APPROVED LAND CORNER

PA 345 OF 1990

Signed by Shelby W. Money Date DECEMBER 2, 1994
Surveyor's Michigan License No. 30092

RAY DAVIS, P.S. CO. SURVEYOR
DATE 12-2-94
LIBER 0005 PAGE 0141

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1980