

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

96 DEC 27 PM 1:03

For corners in

<u>Lapeer</u> (County)	Located In: Almont Township	Corner Code # _____
1. Public Land Survey	T <u>6N</u> R <u>12E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William E. Soderberg, in a field survey on May 7, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1918 Joseph Wampler Set Post No witnesses found
- 7-10-73 LCRC Recorded by Bernard Henderson 16043 in liber 2, page 281 Found 1/2" Iron
- 7-10-73 Survey recorded by Bernard Henderson 16043 in liber 2, page 372 Found 1/2" Iron
- 12-16-75 Survey recorded by Robert Kay 14096 in liber 3, page 485 Found 1/2" Iron
- 7-31-80 Survey recorded by Bernard Henderson 16043 in liber 5, page 950 Set PK from previous witnesses.
- 8-1-89 Survey recorded by Earl Grvlin 23510 in liber 8, page 479 Found 1/2" Iron
- 7-3-90 Survey recorded by Earl Grvlin 23510 in liber 8, page 957 Found 1/2" Iron
- 7-10-93 Lapeer County Road Commission witness book Found 1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found empty monument box near centerline of Bishop Road (In the Dryden Road asphalt apron). 1.4 feet West of line between corner for Dryden Township. Line up with Dryden Road to the East. Found Irons on Survey recorded in Liber 8, Page 479 and ran back to corner. Checks center of found monument box.

Witnesses: from item 2, 3, 4, 5, 6 and 7 above.

- S 20° W 97.44' Found 14" (10") Apple
- S 45° E 41.65' Found P. Pole
- N 30° W 77.94' Found P. Pole

Distances: North to M-5 Dryden Township GLO 79 lks or 52.14 feet; 35.05 feet measured
South to M-6 Dryden Township 2512.46 feet measured

RAY DAVIS P. S. CO. SURVEYOR
DATE 7-16-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard Lapeer County Remonumentation cap stamped " A 5 17635" on 1/2" rebar in existing monument box..

- Az 30° 78.97' Set PK with Lapeer County tag in NW face utility pole
- Az 145° 61.07' Set PK with Lapeer County tag in W face 24" Willow
- Az 275° 154.74' Set PK with Lapeer County tag in N face utility pole
- Az 340° 77.86' Set PK with Lapeer County tag in NE face utility pole

Signed by William E. Soderberg Date 12-19-96
Surveyor's Michigan License No. 17635

