

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 NOV 22 PM 3:56

LIBER NO. 005 ... NO. 299
Richard DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
	ALMONT TOWNSHIP	
1. Public Land Survey	T <u>6N</u> R <u>12E</u>	<u>A-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on May 19, 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1) GLO No point set
- 2) Survey 1973 L. 2, P. 342 Bernard Henderson P.S. 16043 Found Iron
- 3) Survey 1989 L. 8, P. 479 Earl E. Gravin P.S. 23510 Found Iron
- 4) Survey 1990 L. 8, P. 957 Earl E. Gravin P.S. 23510 Found Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rebar on the centerline of Bishop Road Fenceline to the East

Found Witnesses: From Items 2 thru 4 East 24.59' Tel Post
S 45° W 72.31' P. Pole

Distances: A-6 to M-6 (T. 6 N., R 11E.) North 103.23' measured.
A-6 to M-7 (T. 6 N., R 11 E.) South 2445.0' measured.
A-6 to A-7 South 2639.3' measured
A-6 to A-5 North 2615.6' measured

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Lapeer County Remonumentation Brass Cap stamped A-6; 30092 on found 1/2" rebar.

- 60° 33.95' Set PK/Lapeer County tag in Northwest face 15" Aspen
- 105° E 23.92' Set PK/ Lapeer County tag in South face GT box post
- 240° 72.85' Set PK/ Lapeer County tag in Northwest face of utility pole
- 340° 40.50' Set PK/ Lapeer County tag in East face 6" Ash



Signed by *Shelby W. Money* Date Nov 3, 1995
Surveyor's Michigan License No. 30092

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

PEER GROUP
APPROVED LAND CORNER
PA 315 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 7-13-95

LIBER 0005 PAGE 0299